

# इंटरनेट

# मानक

## Disclosure to Promote the Right To Information

Whereas the Parliament of India has set out to provide a practical regime of right to information for citizens to secure access to information under the control of public authorities, in order to promote transparency and accountability in the working of every public authority, and whereas the attached publication of the Bureau of Indian Standards is of particular interest to the public, particularly disadvantaged communities and those engaged in the pursuit of education and knowledge, the attached public safety standard is made available to promote the timely dissemination of this information in an accurate manner to the public.

“जानने का अधिकार, जीने का अधिकार”

Mazdoor Kisan Shakti Sangathan

“The Right to Information, The Right to Live”

“पुराने को छोड़ नये के तरफ”

Jawaharlal Nehru

“Step Out From the Old to the New”

IS 2720-39-1 (1977): Methods of test for soils, Part 39:  
Direct shear test for soils containing gravel, Section 1:  
Laboratory test [CED 43: Soil and Foundation Engineering]



“ज्ञान से एक नये भारत का निर्माण”

Satyanarayan Gangaram Pitroda

“Invent a New India Using Knowledge”



“ज्ञान एक ऐसा खजाना है जो कभी चुराया नहीं जा सकता है”

Bhartrhari—Nitiśatakam

“Knowledge is such a treasure which cannot be stolen”



BLANK PAGE



IS : 2720 ( Part XXXIX/Sec 1 ) - 1977  
( Reaffirmed 2007 )

*Indian Standard*

**METHODS OF TEST FOR SOILS**

**PART XXXIX DIRECT SHEAR TEST FOR SOILS  
CONTAINING GRAVEL**

**Section 1 Laboratory Test**

Third Reprint FEBRUARY 2005

UDC 624.131.377.620.176

© *Copyright* 1978

**BUREAU OF INDIAN STANDARDS**  
MANAK BHAVAN, 9 BAHADUR SHAH ZAFAR MARG  
NEW DELHI 110002

*Indian Standard*  
**METHODS OF TEST FOR SOILS**

**PART XXXIX DIRECT SHEAR TEST FOR SOILS  
CONTAINING GRAVEL**

**Section I Laboratory Test**

---

Soil Engineering Sectional Committee, BDC 23

*Chairman*

PROF DINESH MOHAN

*Representing*

Central Building Research Institute (CSIR),  
Roorkee

*Members*

ADDITIONAL CHIEF ENGINEER      Public Works Department, Government of Uttar  
Pradesh

SHRI D. C. CHATURVEDI ( *Alternate* )

ADDITIONAL DIRECTOR RESEARCH      Railway Board ( Ministry of Railways )  
( RDSO )

DEPUTY DIRECTOR RESEARCH  
( RDSO ) ( *Alternate* )

PROF ALAM SINGH

University of Jodhpur, Jodhpur

LT-COL AVTAR SINGH

Engineer-in-Chief's Branch, Army Headquarters

MAJ R. R. SUDHINDRA ( *Alternate* )

DR A. BANERJEE

Cementation Co Ltd, Calcutta

SHRI S. GUPTA ( *Alternate* )

CHIEF ENGINEER ( D & R )

Irrigation Department, Government of Punjab

DIRECTOR ( IPRI ) ( *Alternate* )

SHRI K. N. DADINA

In personal capacity ( P-820 'P' New Alipore, Calcutta  
700053 )

SHRI A. G. DASTIDAR

In personal capacity ( 5 Hungerford Street, 12/1 Hunger-  
ford Court, Calcutta 700017 )

SHRI R. L. DEWAN

Irrigation Research Institute, Khagaul, Patna

DR G. S. DHILLON

Indian Geotechnical Society, New Delhi

SHRI A. H. DIVANJI

Asia Foundations and Construction (P) Ltd, Bombay

SHRI A. N. JANGLE ( *Alternate* )

DR SHASHI K. GUHATI

Indian Institute of Technology, New Delhi

DR G. V. RAO ( *Alternate* )

SHRI V. G. HEGDE

National Buildings Organization, New Delhi

SHRI S. H. BALCHANDANI ( *Alternate* )

SHRI O. P. MALHOTRA

Public Works Department, Government of Punjab

SHRI J. S. MARYA

Roads Wing, Ministry of Shipping & Transport,  
New Delhi

SHRI N. SEN ( *Alternate* )

( Continued on page 2 )

© Copyright 1978

BUREAU OF INDIAN STANDARDS

This publication is protected under the *Indian Copyright Act* ( XIV of 1957 ) and reproduction in whole or in part by any means except with written permission of the publisher shall be deemed to be an infringement of copyright under the said Act.

## IS : 2720 ( Part XXXIX/Sec 1 ) - 1977

( Continued from page 1 )

<i>Members</i>	<i>Representing</i>
SHRI R. S. MELKOTE	Central Water Commission, New Delhi
SHRI C. SUDHINDRA ( Alternate )	
SHRI T. K. NATARAJAN	Central Road Research Institute ( CSIR ), New Delhi
REPRESENTATIVE	Hindustan Construction Co Ltd, Bombay
RESEARCH OFFICER	Building & Roads Research Laboratory, Chandigarh
SHRI K. R. SAXENA	Engineering Research Laboratories, Hyderabad
SECRETARY	Central Board of Irrigation & Power, New Delhi
DEPUTY SECRETARY ( Alternate )	
DR SHAMSHER PRAKASH*	University of Roorkee, Roorkee
DR GOPAL RANJAN ( Alternate )	
SHRI H. D. SHARMA	Irrigation Research Institute, Roorkee
SUPERINTENDING ENGINEER	Public Works Department, Government of Tamil Nadu
EXECUTIVE ENGINEER ( Alternate )	
SHRI B. T. UNWALLA	Concrete Association of India, Bombay
SHRI T. M. MENON ( Alternate )	
SHRI H. C. VERMA	All India Instruments Manufacturers & Dealers Association, Bombay
SHRI V. K. VASUDEVAN ( Alternate )	
SHRI D. AJITHA SIMHA, Director ( Civ Engg )	Director General, ISI ( Ex-officio Member )

### *Secretary*

SHRI G. RAMAN  
Deputy Director ( Civ Engg ), ISI

## Soil Testing Procedures and Equipment Subcommittee, BDC 23 : 3

### *Convener*

PROF ALAM SINGH                      University of Jodhpur, Jodhpur

### *Members*

SHRI AMAR SINGH	Central Building Research Institute ( CSIR ), Roorkee
LT-COL AVTAR SINGH	Engineer-in-Chief's Branch, Army Headquarters
MAJ R. R. SUDHINDRA ( Alternate )	
DEPUTY DIRECTOR RESEARCH ( SOIL MECHANICS-I ) ( RDSO )	Railway Board ( Ministry of Railways )
ASST DIRECTOR RESEARCH ( SOIL MECHANICS-I ) ( RDSO ) ( Alternate )	
SHRI R. L. DIWAN	Irrigation Research Institute, Khagaul, Patna
DIRECTOR ( I & C )	Beas Dams Projects, Talwara Township
SHRI K. S. PREM ( Alternate )	
SHRI H. K. GUHA	Geologist Syndicate Pvt Ltd, Calcutta
SHRI N. N. BHATTACHARAYA ( Alternate )	
DR SHASHI K. GUHATI	Indian Institute of Technology, New Delhi
SHRI R. K. JAIN	United Technical Consultants (P) Ltd, New Delhi
DR P. K. DE ( Alternate )	
SHRI O. P. MALHOTRA	Building & Roads Research Laboratory, Chandigarh
RESEARCH OFFICER ( BLDG & ROADS ) ( Alternate )	

\*He also represents the Institution of Engineers, India.

( Continued on page 14 )

AMENDMENT NO. 1 SEPTEMBER 1987

TO

IS:2720(Part 39/Sec 1)-1977 METHODS OF  
TEST FOR SOILS

PART 39 DIRECT SHEAR TEST FOR SOILS  
CONTAINING GRAVEL

Section 1 Laboratory Test

(Page 4, clauses 2.1 to 2.6) - Substitute the following for these clauses and renumber the subsequent clauses accordingly:

"2.1 The shear box and its assembly shall conform to requirements given in IS:11593-1986 'Specification for shear box (large) for testing of soils'."

(Pages 6 to 11, Fig. 1 to 4) - Delete.

(BDC 23)

**AMENDMENT NO. 2 OCTOBER 1992  
TO  
IS 2720 ( Part 39/Sec 1 ) : 1977 METHODS OF TEST FOR  
SOILS**

**PART 39 DIRECT SHEAR TEST FOR SOILS CONTAINING  
GRAVEL**

**Section 1 Laboratory Test**

*( Page 13, Appendix A, Proforma for Recording Shear Stage):*

- a) *Col 2* — Substitute the word 'Readings' *for* 'Reading' and subdivide the col as 'a' and 'b'.
- b) *Col 3 and 8* — Insert the word 'Average'.
- c) Subdivide col 7 as 'a' and 'b'.

( CED 23 )

---

Sita Fine Arts Pvt Ltd



*Indian Standard*  
**METHODS OF TEST FOR SOILS**

**PART XXXIX DIRECT SHEAR TEST FOR SOILS  
CONTAINING GRAVEL**

**Section 1 Laboratory Test**

**0. FOREWORD**

**0.1** This Indian Standard ( Part XXXIX/Sec 1 ) was adopted by the Indian Standards Institution on 30 September 1977, after the draft finalized by the Soil Engineering Sectional Committee had been approved by the Civil Engineering Division Council.

**0.2** With a view to establish uniform procedures for the determination of different characteristics of soils and also for facilitating a comparative study of the results, the Indian Standards Institution is bringing out this Indian Standard methods of test for soils ( IS : 2720 ) which is being published in parts. 38 parts of this standard have been published so far. This part [ IS : 2720 ( Part XXXIX/Sec 1 )-1977 ] deals with the laboratory determination by direct shear, the shear strength of soils containing gravel with particle size more than 4.75 mm on with disturbed specimen. The test is of two kinds depending upon the state of samples, namely, laboratory test and *in situ* test. The *in situ* test is being covered separately.

**0.3** In the formulation of the standard due weightage has been given to international co-ordination among the standards and practices prevailing in different countries in addition to relating it to the practices in the field in this country.

**0.4** In reporting the result of a test or analysis made in accordance with this standard, if the final value, observed or calculated, is to be rounded off, it shall be done in accordance with IS : 2-1960\*.

---

**1. SCOPE**

**1.1** This standard ( Part XXXIX/Sec 1 ) covers the method for the laboratory determination by direct shear, of the shear strength of soils containing gravel ( with particle size more than 4.75 mm ).

NOTE — It is recommended that the 300-mm box shall be used for soils containing gravel up to 30 mm size.

---

\*Rules for rounding off numerical values ( revised ).

**IS : 2720 ( Part XXXIX/Sec 1 ) - 1977**

**1.2** The test shall be carried out at natural moisture content. In case, the deposit is likely to get saturated, the test shall be carried out in the saturated condition.

**2. APPARATUS**

**2.1 Shear Box** — ( See Fig. 1 ) of mild steel, totally open at top and bottom of size  $300 \times 300$  mm and deep enough to hold a sample of size  $300 \times 300 \times 150$  mm. The box shall be divided horizontally so that the dividing plane coincides with the central plane of the sample. These two parts shall be accurately attached together by two easily removable screws which pass vertically through the walls of the upper half and fit into the lower half. Suitable spacing screws to separate the two halves of the shear box, when it is assembled for the test by the amounts required for the test shall be provided.

**2.1.1** Suitable holes, about 1.5 mm in diameter shall be provided on the sides of the lower half of the shear box to enable entry of water below the bottom of the soil specimen.

**2.2 Container for Shear Box** — so constructed that it holds the bottom of shear box rigidly with respect to the top half and holds water to surround the shear box when it is placed in the container. A drain cock shall be fitted to the container for filling and draining water.

**2.3 Gripper Plates** — ( See Fig. 2A and 2B ) two pairs of mild steel plates to fit into the shear box; one pair plain and one pair perforated.

**2.4 Top and Bottom Plates** — ( See Fig. 3A and 3B ) two pairs of toothed mild steel plates to fit into the shear box; one pair plain and one pair perforated.

**2.5 Base-Plate** — ( See Fig. 4 ) of mild steel with grooves on its top face, to fit into the shear box.

**2.6 Loading Plate** — A mild steel plate of adequate thickness fitting the shear box which shall distribute the load from a yoke over the specimen normal to the shear plane. The lower face of the loading plate shall have cross grooves.

**2.7 Loading Device** — The major requirements of the loading device are the following:

- a) The vertical stress on the sample shall remain vertical and constant during test. The normal load shall be applied uniformly on the soil specimen in the shear box without eccentricity;
- b) The shear stress or strain shall be applied in the same plane as the dividing plane of the two parts of the shear box;

- c) In case of a stress controlled apparatus, it should be possible to maintain a constant rate of stress increase during the test irrespective of the strain rate; proper arrangement shall be provided to get different rates of stress increase;
- d) In case of strain controlled apparatus, the strain rate shall remain constant irrespective of the stress. Suitable arrangement shall be provided to provide different strain rates; and
- e) No vibrations shall be transmitted to the sample during the test and there shall not be any loss of shear force due to friction between the loading frame and the shear box container assembly.

**2.8 Weights ( If Necessary )** — For providing the normal load through a normal loading device.

**2.9 Proving Ring** — of suitable capacity fitted with dial gauge accurate to 0.002 mm to measure the shear force.

**2.10 Micrometer Dial Gauges** — Accurate to 0.01 mm. Two, suitably mounted to measure the horizontal movement and the other two suitably mounted to measure the compression or expansion of the specimen.

**2.11 Stop Clock**

**2.12 Balance** — of 50 kg capacity sensitive of 1 kg.

### 3. PREPARATION OF SPECIMEN

**3.1** Specimen may be compacted in layers to the required density by a suitable hammer into the shear box after fixing the two halves of the shear box together by means of fixing screws.

### 4. PROCEDURE

**4.1** The shear box with the soil specimen should be fitted into position as shown in Fig. 1. The required normal load shall be applied. After the required normal load is applied, the shear strain shall be applied. Before the application of shear strain, the upper half of the box should be lifted up slightly to eliminate friction between the parts of the shear box. The shear strain should be applied at a constant rate of 0.2 mm/min on the upper half of the box till the failure of the specimen. The final shear shall be recorded through the calibrated proving ring. At the end of the test, the specimen should be removed from the box and the water content at the shear zone should be determined. The process shall be repeated for the next higher normal load. A minimum of 4 sets of readings shall be taken.






FIG. 1 SHEAR BOX ASSEMBLY



All dimensions in millimetres.

2A Gripper Plate ( Plain )


FIG. 2 GRIPPER PLATES — ( Contd )



All dimensions in millimetres.

2B Gripper Plate ( Perforated )

FIG. 2 GRIPPER PLATES




All dimensions in millimetres

3A Plain Plate

FIG. 3 TOP AND BOTTOM PLATES - ( Contd )

IS: 2720 (Part XXXIX/Sec 1) - 1977





All dimensions in millimetres.

3B Perforated Plate

FIG. 3 TOP AND BOTTOM PLATES





All dimensions in millimetres.

FIG. 4 BASE PLATE

**5. CALCULATION AND REPORT**

**5.1** Results of tests shall be recorded suitably. A recommended proforma for recording the result is given in Appendix A.

**5.2** The longitudinal displacement at a particular load shall be recorded from the shear displacement dial readings.

**5.3** The maximum shear force shall be the peak load from load-displacement curve or where the tangent of flatter portion of later part of the curve leaves in case the curve does not give peak point.

**5.4** The maximum shear stress and the corresponding longitudinal displacement ( shear displacement ) and applied normal stress should be recorded for each test and the result should be presented in the form of a graph in which the applied normal stress is plotted as abscissa and the maximum shear stress is plotted as ordinate. The angle which the resulting straight line makes with horizontal axis and the intercept which the straight line makes with the vertical axis shall be reported as the angle of shearing resistance and cohesion intercept respectively.

**NOTE** — The normal stress *versus* maximum shear stress relationship may not be straight line in all cases. In such cases the shear parameter shall be obtained by drawing a tangent to the normal stress and maximum shear stress curve at the point of normal stress expected in the field.

## APPENDIX A

( Clause 5.1 )

### PROFORMA FOR RECORDING TEST RESULTS

Project .. .. .	Location of sample .. .. .
	Sample No. .... .
Rate of shear strain ... .	Proving ring No. .... .
	Proving ring constant ... .
	Weight of loading frame .... .
	Normal load applied ... .

## Soil Specimen Measurements

Dimensions .....	Area of specimen .....
Initial wet mass of specimen .....	Volume of specimen .....
Water content .....	
Bulk density .....	
Final wet mass of specimen .....	
Water content at the shear zone .....	

### Proforma for Recording Shear Stage

i) Thickness of specimen ... mm      ii) Area of cross-section  
of specimen ... cm<sup>2</sup>  
iii) Rate of shearing ... mm/min      iv) Normal stress applied ... kg/cm<sup>2</sup>

DATE AND TIME	SHEAR DISPLACEMENT DIAL READING	SHEAR DISPLACEMENT	PROVING RING READING	SHEAR FORCE	SHEAR STRESS	VERTICAL DIAL READINGS	VERTICAL DISPLACEMENT
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)

Plot — Shear stress *versus* shear displacement and find  
 a) Maximum shear stress at the peak of curve, and  
 b) Corresponding shear displacement.

### Proforma for Recording Summary of Results

TEST NO.	NORMAL STRESS	SHEAR STRESS AT FAILURE	SHEAR DISPLACEMENT AT FAILURE	INITIAL WATER CONTENT	FINAL WATER CONTENT	REMARK
(1)	(2)	(3)	(4)	(5)	(6)	(7)

Plot — Shear stress minus normal stress relationship to obtain

- Cohesion intercept, and
- Angle of shearing resistance.

**IS : 2720 ( Part XXXIX/Sec 1) - 1977**

( Continued from page 2 )

<i>Members</i>	<i>Representing</i>
SHRI R. S. MELKOTE	Central Water Commission, New Delhi
SHRI C. SUDHINDRA ( Alternate )	
SHRI N. SEN	Ministry of Shipping & Transport ( Roads Wing ), New Delhi
SHRI P. K. THOMAS ( Alternate )	
SHRI M. M. D. SETH	Public Works Department, Government of Uttar Pradesh
DR B. L. DHAWAN ( Alternate )	
SHRI P. JAGANNATHA RAO	Central Road Research Institute (CSIR), New Delhi
DR V. V. S. RAO	In personal capacity ( F-24 Green Park, New Delhi )
SHRI H. C. VERMA	Associated Instruments Manufacturers (I) Pvt Ltd, New Delhi
PROF T. S. NAGARAJ ( Alternate )	

## BUREAU OF INDIAN STANDARDS

### **Headquarters:**

Manak Bhavan, 9 Bahadur Shah Zafar Marg, NEW DELHI 110002

**Telephones** 23230131, 23233375, 23239402

**Fax** 91+011 23239399, 23239382

**E - Mail** info@bis.org.in

**website** <http://www.bis.org.in>

### **Central Laboratory:**

Plot No 20/9, Site IV, Sahibabad Industrial Area, SAHIBABAD 201010

### **Telephone**

277 0032

### **Regional Offices:**

Central Manak Bhavan, 9 Bahadur Shah Zafar Marg, NEW DELHI 110002

2323 7617

\*Eastern 1/14 CIT Scheme VII M, V I P Road, Kankurgachi, KOLKATA 700054

2337 8662

Northern SCO 335-336, Sector 34-A, CHANDIGARH 160022

260 3843

Southern C I T Campus, IV Cross Road, CHENNAI 600113

2254 1984

Western Manakalaya, E9, MIDC, Behind Marol Telephone Exchange,  
Andheri (East), MUMBAI 400093

2832 9295

### **Branch Offices:**

'Pushpak', Nurmohamed Shaikh Marg, Khanpur, AHMEDABAD 380001

560 1348

Peenya Industrial Area, 1<sup>st</sup> Stage, Bangalore-Tumkur Road, BANGALORE

839 4955

Commercial-cum-Office Complex, Opp Dushera Maidan, E-5 Arera Colony,  
Bittan Market, BHOPAL 462016

242 3452

62-63, Ganga Nagar, Unit VI, BHUBANESHWAR 751001

240 3139

5<sup>th</sup> Floor, Kovai Towers, 44 Bala Sundaram Road, COIMBATORE 641018

221 0141

SCO 21, Sector 12, Faridabad 121007

229 2175

Savitri Complex, 116 G T Road, GHAZIABAD 201001

286 1498

53/5 Ward No 29, R G Barua Road, 5th By-lane, Apurba Sinha Path,  
GUWAHATI 781003

245 6508

5-8-56C, L N Gupta Marg, Nampally Station Road, HYDERABAD 500001

2320 1084

L-52, Chitaranjan Marg, C-Scheme, JAIPUR 302001

237 3879

117/418 B, Sarvodaya Nagar, KANPUR 208005

223 3012

Sethi Bhawan, 2<sup>nd</sup> Floor, Behind Leela Cinema, Naval Kishore Road,  
LUCKNOW 226001

261 8923

NIT Building, Second Floor, Gokulpat Market, NAGPUR 440010

252 5171

Mahabir Bhavan, 1<sup>st</sup> Floor, Ropar Road, NALAGARH 174101

22 1451

Plot No A-20-21, Institutional Area, Sector 62, Goutam Budh Nagar, NOIDA-201307

240 2206

Patliputra Industrial Estate, PATNA 800013

226 2808

First Floor, Plot Nos 657-660, Market Yard, Gultkdi, PUNE 411037

426 8659

"Sahajanand House" 3<sup>rd</sup> Floor, Bhaktinagar Circle, 80 Feet Road,  
RAJKOT 360002

237 8251

T C No 14/1421, University PO Palayam, THIRUVANANTHAPURAM 695034

233 9174

1<sup>st</sup> Floor, Udyog Bhavan, VUDA, Siripuram Junction, VISHAKHAPATNAM-03

271 2833

\*Sales Office is at 5 Chowringhee Approach, P O Princep Street, KOLKATA 700072

2355 3243

\*Sales Office is at Novelty Chambers, Grant Road, MUMBAI 400007

2309 6528