

इंटरनेट

Disclosure to Promote the Right To Information

Whereas the Parliament of India has set out to provide a practical regime of right to information for citizens to secure access to information under the control of public authorities, in order to promote transparency and accountability in the working of every public authority, and whereas the attached publication of the Bureau of Indian Standards is of particular interest to the public, particularly disadvantaged communities and those engaged in the pursuit of education and knowledge, the attached public safety standard is made available to promote the timely dissemination of this information in an accurate manner to the public.

"जानने का अधिकार, जीने का अधिकार" Mazdoor Kisan Shakti Sangathan "The Right to Information, The Right to Live"

 $\star \star \star \star \star \star \star$

"पुराने को छोड नये के तरफ" Jawaharlal Nehru "Step Out From the Old to the New"

611111111

Made Available By Public. Resource. Org

 $\star \star \star \star \star \star$

मानक

IS 6061-4 (1981): Code of Practice for Construction of Floor and Roof with Joists and Filler Blocks, Part IV: With Precast Hollow Clay Block Slab Panels [CED 13: Building Construction Practices including Painting, Varnishing and Allied Finishing]

"ज्ञान से एक नये भारत का निर्माण″ Satyanarayan Gangaram Pitroda "Invent a New India Using Knowledge"

RIGHT TO INFORMATION "ज्ञान एक ऐसा खजाना है जो कभी चुराया नहीं जा सकता Bhartrhari-Nītiśatakam "Knowledge is such a treasure which cannot be stolen"



BLANK PAGE



PROTECTED BY COPYRIGHT

IS: 6061 (Part IV) - 1981

Indian Standard

CODE OF PRACTICE FOR CONSTRUCTION OF FLOOR AND ROOF WITH JOISTS AND FILLER BLOCKS

PART IV WITH PRECAST HOLLOW CLAY BLOCK SLAB PANELS

UDC 69.024/025:693.28:691.421-478:69.001.3



Copyright 1982

INDIAN STANDARDS INSTITUTION MANAK BHAVAN, 9 BAHADUR SHAH ZAFAR MARG NEW DELHI 110002

son or 3

June 1982

Indian Standard

CODE OF PRACTICE FOR CONSTRUCTION OF FLOOR AND ROOF WITH JOISTS AND FILLER BLOCKS

PART IV WITH PRECAST HOLLOW CLAY BLOCK SLAB PANELS

Building Construction Practices Sectional Committee, BDC 13

Chairman

SHRI C. P. MALIK C-4/38, Safdarjung Development Area, New Delhi

Representing

Members

Shri Suraj S. J. Bahadur	Housing & Urban Development Corporation Ltd, New Delhi
SHRI D. R. BATLIVALA SHRI J. R. BHALLA SHRI M. G. BHARGAVA	Bhabha Atomic Research Centre, Bombay Indian Institute of Architects, New Delhi Public Works Department, Government of Uttar
	Pradesh, Lucknow
SHRI R. K. MATHUR (Alterna	te)
CHIEF ENGINEER (NORTH)	Public Works Department, Government of Punjab, Chandigarh
CHIEF ENGINEER (BLDGS), PWD	Public Works Department, Government of Tamil Nadu, Madras
SUPERINTENDING ENGINEER (SPECIAL BUILDING CIRCLE), PWD, MADURAI (Alternate)	
	Public Works Department, Government of Rajasthan, Jaipur
	Central Public Works Department, New Delhi lternate)
DIRECTOR (ARCHITECTURE), RDSO	Railway Board, Ministry of Railways
JOINT DIRECTOR (ARCHI- TECTURE), RDSO (Alternat	e)

(Continued on page 2)

© Copyright 1982 INDIAN STANDARDS INSTITUTION

This publication is protected under the Indian Copyright Act (XIV of 1957) and reproduction in whole or in part by any means except with written permission of the publisher shall be deemed to be an infringement of copyright under the said Act

IS: 6061 (Part IV) - 1981

(Continued from page 1)	
Members	Representing
SHRI H. S. DUGAL BRIG HARISH CHANDRA (Alter	Builders' Association of India, New Delhi
SHRI T. A. E. D'SA SHRI N. C. DUGGAL (Alternate	Concrete Association of India, Bombay
SHRI R. G. GOKHALE SHRI J. S. KOHLI	State Bank of India, Bombay Engineer-in-Chief's Branch, Army Headquarters, New Delhi
SHRI M. G. VIRMANI (Alternat	
SHRI R. L. KUMAR SHRI K. S. KHARB (Alternate)	Institution of Surveyors, New Delhi
Shri M. Z. Kurien Shri G. K. Majumdar	Tata Consulting Engineers, Bombay Hindustan Prefab Ltd, New Delhi
SHRI H. S. PASRICHA (Alterna	te)
SHRI R. C. MANGAL	Central Building Research Institute (CSIR), Roorkee
SHRI M. P. JAI SINGH (Alterna	ute)
OFFICER-IN-CHARGE	Forest Research Institute & Colleges, Dehra Dun
SHRI R. K. PANDARE	Life Insurance Corporation of India, Bombay
DEPUTY CHIEF ENGINEER (NORTH) (Alternate)	
SHRI T. K. SARAN	Bureau of Public Enterprises (Ministry of Finance), New Delhi
SHRI S. S. KAIMAL (Alternate)	
SHRI S. R. SIVASWAMY	Gammon India Ltd, Bombay
SHRI H. D. MATANGE (Alterna	
SHRI K. S. SRINIVASAN DEPUTY DIRECTOR (Alternate)	National Buildings Organization, New Delhi
SHRI SUSHIL KUMAR	National Buildings Construction Corporation Ltd, New Delhi
PROF C. G. SWAMINATHAN	Central Road Research Institute (CSIR), New Delhi
Shri S. R. Tambe	Public Works & Housing Department, Government of Maharashtra, Bombay
Shri B. T. UNWALLA	Institution of Engineers (India), Calcutta
SHRI G. VENKATESULU	Ministry of Shipping & Transport (Roads Wing), New Delhi
Shri Prafulla Kumar (<i>Alte</i>	rnate)
SHRI G. RAMAN, Director (Civ Engg)	Director General, ISI (Ex-officio Member)
	a .

Secretary

SHRI S. SENGUPTA Assistant Director (Civ Engg), ISI

Floor and Roof Cons	truction Subcommittee, BDC 13:11
Convener	
SHRI D. R. BATLIVALA	Bhabha Atomic Research Centre, Bombay
Members	
Shri S. Adaviyappa	Public Works Department, Government of Rajasthan, Jaipur
SHRI H. N. SAXENA (Alternate	

(Continued on page 12)

.

Indian Standard

CODE OF PRACTICE FOR CONSTRUCTION OF FLOOR AND ROOF WITH JOISTS AND FILLER BLOCKS

PART IV WITH PRECAST HOLLOW CLAY BLOCK SLAB PANELS

6. FOREWORD

0.1 This Indian Standard (Part IV) was adopted by the Indian Standards Institution on 29 December 1981, after the draft finalized by the Building Construction Practices Sectional Committee had been approved by the Civil Engineering Division Council.

0.2 The construction of floor or roof using structural clay blocks is a suitable substitute for *in-situ* RCC slab construction. This type of slab is comparatively cheaper, saves serace materials like cement, steel and provides better thermal insulation. Further, with the setting up of a number of mechanised plants for the manufacture of clay blocks in different parts of the country, this type of prefabricated floor and roof would ensure quicker construction. In this type of floor or roof, the clay blocks are used to prefabricate a slab panel like a wall. It is the clay blocks that take part in the structural action by carrying the flexural compression. The shape of the structural clay blocks are so designed that the slab panels can be used to build the wall. This standard is intended to provide guidance for construction of panel type prefabricated floor or roof slab using hollow clay blocks and is one of a series of Indian Standards on construction of floor or roof with hollow clay blocks.

0.3 In the formulation of this standard assistance has been rendered by the Central Building Research Institute, Roorkee, which supplied valuable technical information.

0.4 For the purpose of deciding whether a particular requirement of this standard is complied with, the final value, observed or calculated, expressing the result of a test or analysis, shall be rounded off in accordance with IS : 2-1960*. The number of significant places retained in the rounded off value should be the same as that of the specified value in this standard.

^{*}Rules for rounding off numerical values (revised).

IS : 6061 (Part IV) - 1981

1. SCOPE

1.1 This standard (Part IV) covers the design and construction of panel type prefabricated floor or roof using hollow clay blocks.

2. MATERIALS

2.1 Cement Concrete — Cement concrete to be used over the support to fill the joint between two consecutive slab panels shall conform to IS: 456-1978*.

2.2 Hollow Clay Blocks (Structural Type) — Hollow clay blocks shall conform to the requirements of IS : 3951(Part II)-1975† with dimensions preferably as given in Fig. 1.

2.2.1 Average crushing strength of the blocks shall not be less than $20N/mm^2$ on the net area with an individual minimum value of $15 N/mm^2$ when tested in accordance with IS : 3951 (Part II)-1975[†].

2.3 Mortar — Mortar used shall be either cement mortar or cement-lime mortar with a minimum compressive strength of 10 N/mm^2 and shall conform to IS : 2250-1981[‡].

2.4 Reinforcement — These shall conform to either IS : 432 (Part I)-1966§ or IS : 1139-1966 or IS : 1786-1979.

3. PREPARATORY WORK

3.1 All supporting elements like walls, pillars, main beams, secondary beams, frames, etc, shall be completed sufficiently early and cured well before the flooring or roofing work is taken up. Plain cement concrete or mortar bed block may be provided over load-bearing walls, if necessary. The top surface of the supporting elements shall be level finished. Attention shall be paid for arrangements necessary for fixing all service pipes, conduits, fixtures, etc, passing through the floor or roof.

^{*}Code of practice for plain and reinforced concrete (third revision).

[†]Specification for structural hollow clay tiles for floors and roofs: Part II Structural type (*first revision*).

[‡]Code of practice for preparation and use of masonry moutar (first revision).

[§]Specification for mild steel and medium tensile steel bars and hard-drawn steel wire for concrete reinforcement: Part I Mild steel and medium tensile steel bars (second revision).

^{||}Specification for hot rolled mild steel, medium tensile steel and high yield strength steel deformed bars for concrete reinforcements (*revised*).

[¶]Specification for cold worked steel high strength deformed bars for *i* concrete reinforcement (second revision).

IS: 6061 (Part IV) - 1981







IS: 6061 (Part IV) - 1981

4. CASTING CURING AND MATURING OF SLAB PANEL

4.1 The slab panels shall be cast with hollow structural clay blocks on a level platform protected from direct sun as well as quick drying action of strong wind.

4.2 The construction of slab panel is like building a brick wall. The slab panel shall be precast by placing thoroughly soaked and skin-dry hollow clay blocks in a row up to the desired length and jointing them with 10 mm thick 1:3 (1 cement: 3 sand) or equivalent cement-lime mortar. The blocks shall be placed with the short face on the platform. A layer mortar shall then be applied over the top surface and reinforcing bar shall be placed in one of the longitudinal, oval-shaped grooves. Next, a layer of mortar shall again be applied so that total thickness of the mortar joint is about 10 mm. Another coarse of clay blocks shall then be laid as before and this operation shall be repeated up to a maximum height of 600 mm (see Fig. 2). Vertical joints shall be broken in each successive coarse by using half units of clay blocks. The face towards which the main reinforcement is placed shall be made to plumb and this face shall form the ceiling face.

4.3 After casting, the slab panel shall be cured with water for a minimum period of 14 days and further air cured for another 14 days.

4.4 The slab panel shall be lifted from the precasting platform only after 28 days to a stacking yard or to the building site for placement. While transporting, the slab panels shall be transported in a vertical position or horizontally with the plumb face containing reinforcement towards the bottom.

4.5 The slab panels shall not be stacked directly on the ground to avoid contamination with clay, etc. The slab panels may be stacked in vertical or horizontal position with the plumbed face towards the bottom. If stacked horizontally one above another, all the props shall be in the same vertical plane.

5. GENERAL DESIGN REQUIREMENTS

5.1 The design of structural clay block slab shall be based on general structural analysis and requirements laid down in 5.2 to 5.8.

5.2 Design Load -- Live load shall be taken as given in IS : 875-1964*.

5.3 Design for Two Stages of Loading—Being a prefabricated scheme, clay block slabs shall be designed for two different stages of loading conditions as given in **5.3.1** and **5.3.2**.

^{*}Code of practice for structural safety of buildings: Loading standards (revised).



FIG. 2 SLAB PANELS BUILT LIKE A WALL USING CLAP BLOCK

5.3.1 First Stage of Loading — In the first stage of loading, the slab panel shall have to sustain, as a simply supported member, the load due to its own weight and some incidental live load. A properly designed slab panel for the second stage of loading shall be able to sustain this load and, hence, no checking for the first stage of loading will be needed.

5.3.2 Second Stage of Loading — The slab panel shall resist the design load as follows:

a) Self weight of slab panel as simply supported, and

IS: 6061 (Part IV) - 1981

b) Other superimposed load like floor finish and live loads under appropriate end conditions.

5.4 Effective Span — The effective span of the slab shall be taken as the clear span plus the effective depth of the slab or centre to centre distance between the two supports, whichever is less.

5.5 Span to Depth Ratio — The effective span to depth ratio of slab shall satisfy the requirements as given in IS : 456-1978*.

5.6 Loading Arrangement — In case of continuous slab over several spans, consideration may be limited to the following combinations of loading:

- a) Bending moment due to self weight of slab simply supported,
- b) Moment due to superimposed dead load on all spans with full design live load on two adjacent spans, and
- c) Moment due to superimposed dead load on all spans with full design live load on alternate spans.

5.6.1 Moment and Shear Coefficients for Continuous Slabs — Unless more exact estimates are made, the slabs which support uniformly distributed load over three or more spans and which do not differ by more than 15 percent of the longest, the bending moments and shear forces used for design shall be obtained by using the coefficients given in Table 1 and Table 2 respectively.

5.6.1.1 For moments at supports, where two unequal span meets or in case where the spans are not equally loaded, the larger of the two values for negative moment at the support shall be taken for design.

5.7 The average crushing strength of structural hollow clay blocks shall be reduced by 20 percent for design purposes to take into account the non-uniformity of fired clay products. Based on this crushing strength, permissible stresses shall be taken in accordance with IS : 456-1978*.

5.8 Shear — Structural hollow clay block slab shall be checked for resistance to shear stress resulting from transverse shear.

5.8.1 Shear Stress Due to Transverse Shear — The shear stress q at any section shall be calculated from the following equation:

$$q = \frac{V}{b \cdot d}$$

where

V = shear force at the section under consideration due to design load,

•Code of practice for plain and reinforced concrete (third revision]).

b = width of the web, and

d = effective depth.

5.8.2 Shear stress in structural clay block slab shall be within the permissible value.

6. ASSEMBLY OF FLOOR OR ROOF

6.1 The slab panels shall be placed side by side abutting each other, over support finished level and the joints between two adjacent slab panels shall be finished with 1:2 (1 cement : 2 sand) cement mortar rule pointed. Any gap between the two adjacent panels shall be filled with mortar from the top.

6.2 Bearing — Bearing for the slab shall be minimum 75 mm in the direction of spanning and minimum 20 mm at the end.

6.3 It is difficult to provide continuity of slab panels in adjacent spans. Where continuity is desired, negative reinforcement may be provided by embedding up to the required length in the longitudinal groove which comes on the top face of the slab panel. This reinforcement shall be kept projecting from the slab panel end by 60 mm. Reinforcement, thus projecting from both sides, shall be lap welded at site. Alternatively, 120 mm wide *in-situ* concrete may be laid in between the two adjacent slab panels and thus partial continuity may be obtained by providing negative reinforcement over the support to the required length on either side within that *in-situ* concrete.

6.4 Constructional Details

6.4.1 Structural clay blocks shall be immersed in water for about 20 to 30 minutes and skin-dry at the time of use. The thickness of mortar joint shall not be more than 12 mm.

6.4.2 Fixtures like junction boxes, floor traps, etc, shall be fixed in solid precast concrete block of same size as the clay block. While building the slab panel, the precast concrete block containing the fixture shall be laid at the appropriate position instead of the clay block. Concealed electrical conduit shall be placed inside the hollow of the clay block along the direction of spanning.

6.4.3 Splicing of reinforcement shall be avoided and minimum cover to reinforcement shall be 12 mm.

7. FINISHING

7.1 The roof or floor may be further finished with the specified roof or floor in accordance with the relevant Indian Standards mentioned in 7.1.1.

IS: 6061 (Part IV) - 1981

TABLE 1 BENDING MOMENT COEFFICIENTS

(Clause 5.6.1)

SL (No. LOADING	IG SPAN MOMENTS		SUPPORT MOMENTS	
		At Middle of End Span	At Middle of Interior Span	At First Interior Support	At All Other Interior Supports
(1)	(2)	(3)	(4)	(5)	(6)
1.	Moments due to dead load and imposed load (fixed)	$+ \frac{1}{12}$	$+ \frac{1}{24}$	$-\frac{1}{10}$	$-\frac{1}{12}$
2.	Moment due to imposed load (not fixed)	$+ \frac{1}{10}$	$+ \frac{1}{12}$	$-\frac{1}{9}$	$-\frac{1}{9}$

NOTE — For obtaining the bending moments, the coefficient shall be multiplied by the total design load and effective span.

TABLE 2 SHEAR FORCE COEFFICIENTS

(Clause 5.6.1)

SL I	No. LOADING	AT END SUPPORT	FIRST INTERIOR SUPPORT		AT ALL OTHER INTERIOR SUPPORTS
			Outer Side	Inner Side	INTERIOR DUFFORTS
(1)	(2)	(3)	(4)	(5)	(6)
1.	Dead load and imposed load (fixed)	0.4	0.6	0.52	0.2
2.	Imposed load (not fixed)	0.42	0.6	0.6	0.6

NOTE - For obtaining the shear force, the coefficient shall be multiplied by the total design load.

7.1.1 Indian Standards covering floor or roof finishes so far published are enlisted below:

Sl No.	Type	<i>IS</i> :
1.	Magnesium oxychloride	658-1962*
2.	Bitumen mastic	1196-19 78 †
3.	Rubber	1197-1970‡
4.	Linoleum	119 8- 1958§
5.	Cement concrete tiles	1443-1972
6.	Terrazzo	2114-1962¶
7.	Mud PHUSKA	2115-1980**
8.	In-situ cement concrete	2571-1970††
9.	Epoxy resin	4631-1968‡‡
10.	PVC	53 18- 1969§§
11.	Brick	5766-1970

7.2 The ceiling may be rendered (see IS: 2402-1963¶¶) or plastered (see IS: $1661-1972^{***}$) as may be necessary. The blocks shall be thoroughly wetted before rendering or plastering.

7.3 The waterproofing of the roof may be done in accordance with either IS : $1346-1976\uparrow\uparrow\uparrow\uparrow$ or IS : $3036-1965\ddagger\ddagger$ or IS : 4365-1967 or IS : $7290-1973\parallel\parallel\parallel\parallel$.

*Code of practice for magnesium oxychloride composition floors (revised).

+Code of practice for laying bitumen mastic flooring (second revision).

Code of practice for laying of rubber floors (first revision).

§Code of practice for laying and maintenance of linoleum floors.

Code of practice for laying and finishing of cement concrete flooring tiles (first revision).

¶Code of practice for laying in-situ terrazzo floor finish.

**Code of practice for flat-roof finish: Mud PHUSKA (second revision).

††Code of practice for laying in-situ cement concrete flooring (first revision).

‡‡Code of practice for laying of epoxy resin floor toppings.

§§Code of practice for laying of flexible PVC sheet and tile flooring.

Code of practice for laying burnt clay brick flooring.

¶Code of practice for external rendered finishes.

***Code of practice for application of cement and cement-lime plaster finishes (first revision).

t+tCode of practice for waterproofing of roofs with bitumen felts (second revision).
tttCode of practice for laying lime concrete for a waterproofed roof finish.

§§§Code of practice for application of bitumen mastic for waterproofing of roofs.

Recommendation for use of polyethylene film for waterproofing of roofs.

(Continued from page 2)				
Members	Representing			
SHRI S. C. CHAKRABARTI	Central Building Research Institute (CSIR), Roorkee			
SHRI N. C. MAJUMDAR (Alte	rnate)			
Shri K. Devarajan	Engineer-in-Chief's Branch, Army Headquarters, New Delhi			
Shri Ravinder Sharma (Al	ternate)			
DEPUTY CHIEF ENGINEER	Railway Board, Ministry of Railways			
(GENERAL), SOUTHERN				
RAILWAY, MADRAS				
SHRI Y. R. KHIRWADKAR	Indian Institute of Architects, Bombay			
SHRI F. B. PITHAVADIAN (Al	ternate)			
SHRI R. L. KUMAR	Institution of Surveyors, New Delhi			
SHRI K. S. KHARB (Alternate SHRI G. K. MAJUMDAR				
SHRIG. K. MAJUMDAR	Hindustan Prefab Ltd, New Delhi			
SHRI H. S. PASRICHA (Alterna	nte)			
Shri M. S. Moitra	Calcutta Metropolitan Development Authority, Calcutta			
SHRI B. V. B. PAI	Concrete Association of India, Bombay			
SHRIN. C. DUGGAL (Alternat	e)			
SHRI R. RAJAPPA	Tata Consulting Engineers, Bombay			
Dr M. Ramaiah	Structural Engineering Research Centre (CSIR), Madras			
SHRI Z. GEORGE (Alternate)				
SENIOR DEPUTY CHIEF ENGINEER	Public Works Department, Government of Tamil			
(BLDGS)	Nadu, Madras			
EXECUTIVE ENGINEER				
(PLANNING) (Alternate)				
SHRI K. S. SRINIVASAN SHRI SASHI KANT (Alternate)	National Buildings Organization, New Delhi			
SUPERINTENDING ÈNGINEER, (ROAD & BLDGS)	Public Works Department, Government of Andhra. Pradesh, Hyderabad			
SURVEYOR OF WORKS, MADRAS				
CENTRE CINCLE				