

X

इंटरनेट

Disclosure to Promote the Right To Information

Whereas the Parliament of India has set out to provide a practical regime of right to information for citizens to secure access to information under the control of public authorities, in order to promote transparency and accountability in the working of every public authority, and whereas the attached publication of the Bureau of Indian Standards is of particular interest to the public, particularly disadvantaged communities and those engaged in the pursuit of education and knowledge, the attached public safety standard is made available to promote the timely dissemination of this information in an accurate manner to the public.

"जानने का अधिकार, जीने का अधिकार" Mazdoor Kisan Shakti Sangathan "The Right to Information, The Right to Live"

"पुराने को छोड नये के तरफ" Jawaharlal Nehru "Step Out From the Old to the New"

Made Available By Public.Resource.Org

51111111

मानक

IS 784 (2001): Prestressed Concrete Pipes (Including Fittings) - [CED 53: Cement Matrix Products]



"ज्ञान से एक नये भारत का निर्माण″ Satyanarayan Gangaram Pitroda "Invent a New India Using Knowledge"

"ज्ञान एक ऐसा खजाना है जो कभी चुराया नहीं जा सकता Bhartrhari-Nītiśatakam "Knowledge is such a treasure which cannot be stolen"





BLANK PAGE



PROTECTED BY COPYRIGHT

IS 784: 2001

भारतीय मानक

REAFFIRMED AUG 2010

पूर्वप्रबलित कंक्रीट पाइप (विशेष सहायकांग सहित) - विशिष्टि *(दूसरा पुनरीक्षण)*

Indian Standard

PRESTRESSED CONCRETE PIPES (INCLUDING SPECIALS) - SPECIFICATION

(Second Revision)

(First ReprintJULY 2004)

ICS 23.040.50; 9I.100.30

© BIS 2001

BUREAU OF INDIAN STANDARDS MANAK BHAVAN. 9 BAHADUR SHAH ZAFAR MARG NEW DELHI 110002

AMENDMENT NO. 1 MARCH 2003 TO IS 784 : 2001 PRESTRESSED CONCRETE PIPES (INCLUDING SPECIALS) — SPECIFICATION

(Second Revision)

(Page 8, clause 13.3) — Substitute the following for the existing:

'13.3 Permeability Test on Coating

The permeability test when conducted in accordance with the method described in IS 3597 shall meet the requirement of final permeability. The final permeability shall not exceed 0.3 cm^3 '

NOTE — It is recommended that initial absorption should not exceed 2.0 cm³ and the difference in any two readings during initial absorption should not be more than 0.8 cm³

(CED 53)

Printed at Prabhat Offset Press, New Delhi-2

AMENDMENT NO. 2 SEPTEMBER 2005 TO

.

IS 784: 2001 PRESTRESSED CONCRETE PIPES (INCLUDING SPECIALS) — SPECIFICATION

(Second Revision)

(Page 2, clause 4.3) — Substitute the following for the existing:

'4.3 Water

Water used for mixing of concrete and curing of pipes shall conform to 5.4 of IS 456.'

(Page 2, clause 4.6) — Substitute the following for the existing:

4.6 Steel for Cylinder, Joint Rings and Specials

Steel plates for cylinders, joint rings and specials shall conform to IS 2062.'

(Page 6, clause 9.1.1) — Add the following at the end of the clause:

"Alternatively, steel joint rings suitable for site welding may be adopted. The thickness of plate for steel joint rings of Prestressed Concrete Cylinder Pipes shall be as given below:

Minimum wall thickness
of joint rings
mm
5.0
5.0
5.0
5.0
5.0
5.0
5.0
5.0
5.0
5.0
5.0

1

Amend No. 2 to IS 784 : 2001

1 000	7.0
1 100	7.0
1 200	8.0
1 300	8.0
1 400	8.0
1 500	8.0
1 600	10.0
1 700	10,0
1 800	10.0
1 900	12.0
2 000	12.0
2 100	12.0
2 200	12.0
2 300	14.0
2 400	14.0
2 500	14.0

(Page 7, clause 9.1.2) — Add the following at the end of the clause:

'The minimum wall thickness of steel cylinders shall be 1.6 mm.'

(Page 7, clause 11.1) — Substitute the following for the existing:

'11.1 Unless otherwise specified, joints between pipes shall be of spigot and socket type with rubber ring or with steel joint rings embedded at ends for site welding. In case of pipes for culverts, joints may be spigot and socket, roll on gasket joint, confined gasket joint or flush joint. The joint shall be designed such that it will be water tight under all service conditions. Joint design shall be furnished by manufacturer before undertaking manufacture. The rubber ring joint design, shall take into consideration the tolerance for rubber cord, tolerance for socket and spigot diameters, allowable deflection at joint and permanent set in the rubber ring.'

(Page 7, clause 13.1) --- Substitute the following for the existing:

'13.1 Design Proving and Manufacturing Process Approval Test in Factory

As soon as 4 to 5 pipes are made, at least 2 to 3 pipes shall be installed and site pressure test shall be conducted, to prove and finalize pipe and joint design and joint dimension tolerances, etc. For one diameter and different pressure, only the test for the highest pressure shall be done. For this test no external load should be applied.⁵

Amend No. 2 to IS 784 : 2001

(Page 9, clause 15.1.1) - Substitute the following for the existing:

'15.1.1 Internal Diameter

.

The internal diameter shall be measured at each end of the pipe at approximately 50 mm from the ends and also at centre (for internal diameter above 700 mm). Two measurements of internal diameter at 90° to each other shall be made at each end and at centre.

To accomplish this 'Go' and 'No Go' gauges of a stiff rod with hardened rounded ends shall be used. The length of gauges and colour shall be as given below:

Length	Colour

Gauges for ends:

'Go'	1 mm less than the diameter after applying -ve tolerance	Green
'No Go'	1 mm more than the diameter after applying +ve tolerance	Orange

Gauges for centre (for internal diameter of pipes above 700 mm):

'Go'	1 mm less than the diameter after applying - ve tolerance	Green with white bands
'No Go'	1 mm more than the diameter after applying +ve tolerance	Orange with white bands

3

Amend No. 2 to IS 784 : 2001

Example:

Suppose theoretical diameter of pipe = 1 200 mm and length of pipe is 5 m

	Tolerance			Length of
Ends	±9	'Go'	1 200 - 9 - 1	= 1 190
		'No Go'	1 200 + 9 + 1	= 1 210
Center	±12	'Go'	1 200 - 12 - 1	= 1 187
		'No Go'	1 200 + 12 + 1	= 1 213

(*Page* 15, *Annex* D, *clause* D-3.10) — Substitute the following for the existing under heading 'Compressive' column of 'Permissible' against loading combination b):

 $0.5 \times f_{p2} = 0.5 \times 25 = 12.50$

(*Page* 15, *Annex* D, *clause* D-3.10) — Substitute the following for the existing under heading 'Compressive' column of 'Permissible' against loading combination (c):

$$0.5 \times f_{ok} = 0.5 \times 40 = 20.00$$

(*Page* 15, *Annex* D, *clause* D-3.10) — Substitute the following for the existing under heading 'Compressive' column of 'Permissible' against loading combination (d):

 $0.5 \times f_{pl} = 0.5 \times 15 = 7.50$

(*Page 15, Annex D, clause* **D-3.10**) — Substitute the following for the existing under heading 'Compressive' column of 'Permissible' against loading combination (e):

4

$$0.5 \times f_{ck} = 0.5 \times 40 = 20.00$$

Amend No. 2 to IS 784 : 2001

. .

•

(Page 17, Annex F, clause F-2, Sl No. 2) — Substitute the following for the existing:

...

 $\sqrt{2}$. Relaxation of wire $0.08 f_{\rm sl long} = 0.08 f_{\rm sl}$

(Page 17, Annex F, clause F-2, Sl No. 3) — Substitute the following for the existing:

13. Deformation due to creep $2.5 f_{ex} \log 2.5 f_{ex}$

Reprography Unit, BIS, New Delhi, India

FOREWORD

This Indian Standard (Second Revision) was adopted by the Bureau of Indian Standards, after the draft finalized by the Cement Matrix Products Sectional Committee had been approved by the Civil Engineering Division Council

This standard was published in 1959 and subsequently revised in 1978 to introduce prestressed concrete cylinder pipes, requirements of fittings, provision of more details on design criteria for the pipes, etc

This standard lays down the requirements of prestressed concrete pipes primarily used for the conveyance of water and sewerage and specials for use with them. Two types of prestressed concrete pipes are covered by this specification, namely, prestressed concrete cylinder pipes and prestressed concrete non-cylinder pipes.

This second revision incorporates number of modifications, the most significant of them being

- a) modifications in design and other aspects,
- b) inclusion of typical worked out examples of design,
- c) inclusion of detailed inspection procedure, and
- d) increase in range of diameters of pipes

In the formulation of this standard, assistance has been derived for EN 642 1994 Prestressed Concrete Pressure Pipes, Cylinder and Non-Cylinder, European Committee for Standardization (CEN)

The composition of the technical committee responsible for formulation of this standard is given at Annex K

For the purpose of deciding whether a particular requirement of this standard is complied with, the final value, observed or calculated, expressing the result of a test or analysis, shall be rounded off in accordance with IS 2 1960 'Rules for rounding off numerical values (*revised*)' The number of significant places retained in the rounded off value should be the same as that of the specified value in this standard

Indian Standard PRESTRESSED CONCRETE PIPES (INCLUDING SPECIALS) — SPECIFICATION

(Second Revision)

1 SCOPE

This standard covers the requirements of prestressed concrete pipes (including specials) with nominal internal diameter in the range of 200 mm to 2 500 mm (see Note under Table 1), in which permanent internal stresses are deliberately introduced by tensioned steel to the desired degree to counteract the stresses caused in pipe under service

2 REFERENCES

The standards listed in Annex A contain provisions which through reference in this text constitute provisions of this standard At the time of publication, the editions indicated were valid All standards are subject to revision and parties to agreement based on this standard are encouraged to investigate the possibility of applying the most recent edition of the standards indicated in Annex A

3 TFRMINOLOGY

For the purpose of this standard, the following definitions shall apply

3 1 Prestressed Concrete Cylinder Pipe — A welded sheet steel cylinder with steel socket and spigot rings welded to its ends, lined with concrete suitably compacted and circumferentially prestressed to withstand internal pressure and external design loads and subsequently coated with cement mortar or concrete to protect the steel cylinder and prestressing wires

3.2 Prestressed Concrete Non-Cylinder Pipe — A suitably compacted concrete core longitudinally prestressed with pretensioned high tensile steel wire embedded in the concrete, circumferentially prestressed and coated with cement mortar or concrete to protect the circumferential prestressing wire, to withstand internal pressure and external design loads

3.3 Specials — All items in the pipeline other than straight pipes of standard length, such as bends, air valves and scour valve tees, etc, are classified as specials

3.4 Working Pressure — The maximum sustained internal pressure excluding surge to which each portion of the pipeline may be subjected when installed

3.5 Site Test Pressure — 1.5 times working pressure pertaining to the section or 1.1 times static pressure, whichever is more (surge pressure is to be controlled within 25 percent of pump head in case of pumping main)

3.6 Factory Test Pressure

- a) Site test pressure + 0 1 N/mm², for working pressure upto 1 N/mm², and
- b) Site test pressure + 0 2 N/mm², for working pressure above 1 N/mm²

3.7 Surge (Water Hammer) Pressure

It is a pressure which is produced by a change of velocity of the moving stream and becomes maximum when there is sudden stoppage which may be caused by the closing of a valve or by shutting down a pump station Surge pressure is to be controlled within 25 percent of pump head

4 MATERIALS

4.1 Cement

The cement used in the manufacture of prestressed concrete pipes and specials shall be one of the following

- a) 43 grade ordinary Portland cement conforming to IS 8112
- b) 53 grade ordinary Portland cement conforming to IS 12269
- c) Rapid hardening Portland cement conforming to IS 8041
- d) Portland slag cement conforming to IS 455 with slag not more than 50 percent
- e) Sulphate resisting Portland cement conforming to IS 12330

 $\label{eq:NOTE-Subplate} NOTE-Subplate resisting Portland cement shall be used where subplate is predominant$

4.2 Aggregates

The aggregates shall conform to IS 383 The provision of 4 (Grading) of IS 383 shall not apply Manufacturer shall furnish the grading curve for coarse and fine aggregates which he proposes to use The variation in fineness modulus during manufacture shall not be more than ± 5 percent Silt content in fine aggregates shall be less than 3 percent The fineness modulus of the aggregates for coating shall be between 2 6 to 3 2

4.3 Water

Water used for concrete, cement mortar and for curing the pipes shall be free from injurious amounts of oil, acid, strong alkaline scales and vegetable matter and shall be able to make concrete of satisfactory strength requirements

4.4 Admixtures

Admixtures may be used with the approval of the purchaser However, use of any admixture containing chlorides in any form shall be prohibited The admixtures shall conform to IS 9103

4.5 Steel for Reinforcement

4.5.1 Prestressing Steel

Prestressing steel wire shall conform to IS 1785 (Part 1) or IS 1785 (Part 2) or IS 6003 or IS 6006 For longitudinal prestressing, wire having tensile strength, less upto 15 percent of ultimate tensile strength, may be used, if required This is to avoid excessive wear of rollers for threading, or cracking of wire during button heading for end anchors

4.5.2 Untensioned Reinforcement

Untensioned reinforcement may consist of mild steel conforming to IS 432 (Part 1) or IS 432 (Part 2) or high strength deformed bars conforming to IS 1786 or plain hard drawn steel wire conforming to IS 1785 (Part 1) and IS 1785(Part 2) or welded wire fabric conforming to IS 1566

4.6 Steel for Cylinders and Specials

Steel plates for cylinders and specials shall conform to IS 2062

4.7 Rubber Sealing Rings

4.7.1 Rubber sealing rings shall comply with IS 5382 The manufacturer of pipe shall examine each sealing ring visually for defects, particularly at the joints

4.7.2 Every scaling ring shall be clearly marked The marking shall indicate the chord diameter, internal diameter of the ring and name of the manufacturer of rubber scaling rings

4.7.3 In case of splices, each splice shall be thoroughly visually checked by twisting the ring through 360° Splices showing visible separation or cracks shall be rejected Not more than two splices in each ring shall be permitted All sealing rings shall be protected from direct rays of the sun and stored in dry place

Following composition of natural rubber is recommended for sealing rings

Natural rubber content as compound	75 0 percent by mass, Min
Ash	6 0 percent by mass, Max
Total sulphur	3 0 percent by mass, Max
Acetone extract	8 0 percent by mass, Max
Sulphur in acetone extract	0 6 percent by mass, Max
Alcohol potash extract	1 5 percent by mass, Max
Filler	Carbon black only
Accelerators	As required

The compounding ingredients listed below shall be added to the composition in the proportions (given based on 100 parts by mass of raw rubber)

Waxes (melting point	0 5 parts by mass, Min
57° C Min)	1 5 parts by mass, Max
Napthenic process oil	2 5 parts by mass, Max
Anti-oxidant	1 5 parts by mass, Min

4.8 Bitumen or Other Protective Coating

The purchaser may specify the application of an external or internal bituminous epoxy or other approved coating to be applied When the pipes are to be used for carrying potable water, the inside coating shall not contain any constituents soluble in such water or any ingredient which could impart any taste or odour to the potable water

5 DIMENSIONS AND TOLERANCES

5.1 Nominal internal diameter of the pipes and minimum core thickness shall be as given in Table 1

5.2 Length

Effective length of pipes shall be 2 m to 6 m However, the preferred effective lengths should be 2, 2 5, 4, 5 and 6 m For pipes upto and including 300 mm diameter, the effective length shall not be more than 3 m

5.3 Tolerance

5.3.1 Length

Tolerance on length shall be ± 1 percent of the specified length

5.3.2 Internal Diameter

For pipes of length less than 4 m, the tolerance shall be ± 5 mm for diameter upto and including 350 mm For diameter above 350 mm, the tolerance shall be ± 10 mm For pipes of length 4 m and above, the tolerance shall be as given below

Internal Diameter	Tolerances	
	In areas within 600 mm of an end of the pipe	Over rest of the pipe
	mm	mm
Up to 900 mm	± 6	± 9
Over 900 mm and upto 1 600 mm	± 9	± 12
Over 1 600 mm	± 12	± 12

Table 1 Nominal Internal Diameter and Minimum Core Thickness of Pipes

(Clause 51)

Nominal Internal Diameter of Pipe mm	Minimum Core Thickness mm	Nomiani Internal Diameter of Pipe mm	Minimum Core Thickness mm
(1)	(2)	(3)	(4)
(1)	(2)	(5)	(4)
200	35	1 300	/5
250	35	1 400	75
300	35	1 500	80
350	35	1 600	85
400	35	1 700	90
450	35	1 800	95
500	35	1 900	100
600	40	2 000	105
700	40	2 100	110
800	45	2 200	115
900	55	2 300	120
1 000	60	2 400	125
1 100	65	2 500	130
1 200	70		

NOTES

1 Internal diameter of pipes other than those mentioned in this table may be supplied by mutual agreement between the purchaser and the manufacturer. For higher pressure the core thickness have to be increased, in such cases.

- a) the diameter will be correspondingly reduced (This is to enable use of same moulds) and
- b) multiple layers of circumferential prestressing wire shall be adopted

2 This standard includes provision upto 2 500 mm diameter pipes Pipes of diameter beyond 2 500 mm may be supplied in special cases by mutual agreement between purchaser and manufacturer subject to additional precautions taken in design, manufacture testing and construction of the pipe

5.3.3 Core Thickness

The core thickness shall not be less than the design thickness by more than 5 percent The manufacturer shall declare the core thickness and the above tolerance shall be applicable to that core thickness

6 JOINT DIMENSIONS

Joint dimensions with tolerances for socket and spigot

diameters shall be furnished by the manufacturer for inspection The indicative dimensions of socket and spigot are given in Annex B

7 DESIGN

7.1 Information to be supplied by purchaser is given in Annex C

7.2 All pipes shall be designed to withstand the combined effects of internal water pressure and external loads

7.3 The design of the prestressed concrete pipes shall cover all such stages, which may induce stresses in any section of the pipe For investigation of these design stages, the likely extreme conditions of stresses shall be considered in the order of their occurrence, during the process of manufacture, handling, erection and under service

7.4 Design Criteria for Non-Cylinder Pressure Pipes

The pipes shall be designed to meet the requirements given in subsequent clauses

7.4.1 Longitudinal Prestressing Requirements

The permissible stresses for various load combinations shall be as follows

	Tension N/mm ²	Compression N/mm ²
Longitudinal prestress (after losses) in barrel		Minimum residual compression of 2 5 N/mm ² for upto and inclu- ding pipe dia 600 mm and 1 0 N/mm ² for dia above 600 mm
Longitudinal prestress during circumferential prestressing (temporary)	0 56 fp ^{0 5}	0 5 fp
Longitudinal prestress after losses plus beam action	0 34 f _{ck} ^{0 5}	0 5 f _{ck}
Handling	0 67 N/mm ²	05fp
Transport and unloading where	0 56 f _{ck} ^{0 5}	0 5 f _{ck}
	Longitudinal prestress (after losses) in barrel Longitudinal prestress during circumferential prestressing (temporary) Longitudinal prestress after losses plus beam action Handling Transport and unloading where f_{a} = Characteris	Longitudinal — prestress (after losses) in barrel — Longitudinal 0 56 $f_p^{0.5}$ prestress during circumferential prestressing (temporary) Longitudinal 0 34 $f_{ck}^{0.5}$ prestress after losses plus beam action — Handling 0 67 N/mm ² Transport and 0 56 $f_{ck}^{0.5}$ unloading where f_{c} = Characteristic compress

- concrete at p days in N/mm², and
- f_{ck} = Characteristic compressive design strength of concrete in N/mm²

IS 784 : 2001

NOTES

I Longitudinal stresses induced in the core during circumferential prestressing shall be treated as temporary and shall be equal to 0 284 times initial compressive stress induced in core

2 For longitudinal stress due to beam action, a pipe shall be assumed to span its full length and support a total load per meter in Newtons equal to the self weight the weight of the water in the pipe and earth load equivalent to 2.2 times the outside diameter of pipe (in mm)

3 For calculation of number of longitudinals for transport and unloading conditions, following bending moment shall be considered for effective length of pipes upto 5 meter and diameter upto 600 mm

Dia	Bending Momen
mm	N mm
200	3 04 × 107
250	3 78 × 107
300	4 59 × 107
350	5 45 × 107
400	6 37 × 107
450	7 36 × 10 ⁷
500	8 44 × 10 ⁷
600	11 08 × 107
wing effective	length more than 5 m, the h

For pipes having effective length more than 5 m, the bending moment shall be multiplied by a factor (*J/S*)² where *L* is the effective length of pipe. For pipes above 600 mm diameter no special consideration is necessary. The minimum number of longitudinals for 4 m and 5 m long pipes shall be 12 and 16 respectively.

7.4.2 Typical calculation for the design of longitudinals for pipe diameter 600 mm and below is given in Annex D $\,$

7.4.3 Circumferential Prestressing Requirements

The permissible stresses for various load combinations shall be as given below

Description of Loading		Permissible Stresses			
	Combination	Tension N/mm ²	Compression N/mm ²		
a)	Circumferential prestressing condition (Self weight + Initial prestress)	0	0 55 fp		
b)	Site test condition (Site test pressure + Self weight + Weight of water + Earth fill + Final prestress)	0 13 f _{ck} ^{0 67}	0 45 <i>f</i> ck		
c)	Factory test con- dition (Factory test pressure + Self weight + Weight of water + Pre-stress at factory test)	0 13 f _{ck} ^{0 67}	0 45 <i>f</i> ck		
d)	Operating condition (Working pressure+ Self weight + Weight of water + Earth fill + final prestress)	0	0 45 <i>f</i> ck		

Description of Loading Combination	Permissible Stresses				
	Tension N/mm ²	Compression N/mm ²			
e) Operating con-	0 13 fck ^{0 67}	0 45 fck			

e) Operating con 0 13 f_{ck}
 dition + Live load
 (with impact)

where

- f_p = Characteristic compressive strength of concrete at p days in N/mm²
- f_{ck} = Characteristic compressive design strength of concrete in N/mm²

NOTES

1 The total tensile stress in the core shall be considered as the sum of the hoop stress and flexural stresses, without the application of any reduction factor

2 When calculating hoop stress, only core thickness should be considered When calculating ovalization flexural stress the sum of the core and coating thickness should be considered

3 For calculating bending moments and thrusts for external loads Olander s coefficients are to be used The values for bedding angles from 30° to 180° are given in Annex E

4 When submitted to factory test the mortar or concrete coated pipe shall not have cracks in the coating wider than 0 1 mm for more than 300 mm length

7.5 Loss of prestress in circumferential and longitudinal wires shall be calculated as per Annex F

7.6 Typical design of prestressed concrete pipe, with winding by process of counter weight/break is given in Annex G

7.7 Typical design of prestressed concrete pipe with winding by process of die is given in Annex H

7.8 Typical design of prestressed concrete pipe for drainage, sewerage and culverts is given in Annex J

7.9 Design Criteria for Cylinder Pipes

The pipes shall be designed to meet the following conditions

Description of Loading	Permissible Stresses			
combination	Tension N/mm ²	Compression N/mm ²		
a) Circumferential prestressing condition (Self weight + Initial prestress)	0	0 55 ƒ _P		
b) Site test condition (Site test pressure + Self weight + Weight of water + Earth fill + Final prestress)	0 38 fck ^{0 67}	0 45 <i>f</i> ck		

Description of Loading Combination	Permissible Stresses					
	Tension N/mm ²	Compression N/mm ²				
c) Operating condition (Working pressure+ Self weight + Weight of water + Earth fill + Final prestress)	0	0 45 f _{ck}				
d) Operating condi- tion + Live load (with impact)	0 38 f _{ck} ^{0 6}	7 0 45 f _{ck}				
where						
$f_p = Characteristicconcrete at p of$: compress lays in N/m	ive strength of				
f_{ck} = Characteristic of concrete in	f_{ck} = Characteristic compressive design strength of concrete in N/mm ²					

8 MANUFACTURE

8.1 Core

8.1.1 Moulds

The moulds and method of manufacture of pipe shall be such that the form and dimensions of the finished pipe conform to the requirements given in 5 and 12 and the surface and edges are clean and true

8.1.2 Concrete Mix

The proportions of cement, fine aggregate, coarse aggregate and water used in concrete for pipe core shall be determined and controlled as the work proceeds to obtain homogenous, dense, workable, durable concrete of specified strength in the pipe, and minimum defects on the surface of the pipe The proportions shall be those, that will give the best overall results with the particular materials and the methods of placing used for the work A minimum of 350 kg/m³ of cement shall be used for concrete The water cement ratio shall be such, as to ensure that the concrete will meet the strength requirements, but in no case it shall exceed 0.5 The soluble chloride ion content of the concrete or mortar mix, expressed as a percentage of the mass of cement shall not exceed 0.20 percent

Unless the design calls for higher concrete strength, the minimum compressive strength of concrete shall not be less than 40 N/mm² at 28 days

8.1.3 Placing of Concrete

The concrete in the cores may be placed either by the centrifugal method, vertical casting method, or by other approved methods. For centrifugal spinning method, concrete shall be deposited in the mould and the speed of rotation during placing shall be such, that concrete will be evenly distributed The same is sufficiently compacted at the specified thickness throughout the length of the pipe After the concrete has been deposited, the rotation shall be continued at an increased speed, for a length of time sufficient to provide the specified strength, sufficient compaction and bond, to permit handling of the mould from the spinning machine, without damage to the pipe core Excess water and laitance shall be removed from the interior surface of the pipe in an approved manner so that the surface is solid, straight and true

8.2 Curing of Core and Cover Coat

The curing of the concrete core and that of cover coat shall be in two separate operations The curing for core shall be for a period, till it attains the required strength

Curing shall be either by steam or by water or by a combination of steam and water, or by use of approved curing compounds Coating shall be cured for a minimum period of 7 days, if water curing is used If steam curing is used for coating, after that it should be water cured for at least 3 days

8.3 Pretensioning and Release of Longitudinal Wires

The concrete core shall be longitudinally prestressed, including the socket, by means of high tensile steel wires or strands, which shall be provided with permanent anchorages embedded in the concrete, within the joint portion at each end The centreline spacing between the longitudinal wires measured along the barrel shall not exceed twice the core thickness or 150 mm, whichever is greater, subject to the provision of **7.4.1**(c)

The clear cover of concrete over all steel reinforcement including the ends of the longitudinal prestressing wires, shall be such that in any finished pipe it is nowhere less than 12 mm

8.3.1 The longitudinal wires shall be stressed to the designed tension, taking into account the loss of stress in wire The tension shall be maintained by positive means till detensioning

8.3.2 The tensioned wires shall not be released until the concrete in the core has attained a compressive strength of at least two times the initial longitudinal prestress or 15 N/mm² whichever is greater

8.4 Circumferential Prestressing

8.4.1 Circumferential prestressing shall not take place until the concrete in the core has reached a minimum compressive strength of 25 N/mm², or as per the design requirements whichever is greater

IS 784 : 2001

8.4.2 The initial stress in the wire during circumferential winding shall not be more than 75 percent of the minimum ultimate tensile strength of wire, when counter-weight or break system is used for developing tension. If tension is developed by use of a die, then the initial stress in the wire shall not exceed 65 percent of the ultimate tensile strength of wire

8.4.3 The initial compressive stress induced in the core concrete shall not exceed 55 percent of the compressive strength of the concrete in the pipe at the time of transfer

8.4.4 Methods and equipments for wrapping the wire shall be such that wire shall be wound around the core in a helical form at the predetermined design spacing and capable of controlling the tension. Wire splicing shall be capable of withstanding a force equal to the full strength of wire At the ends of core pipe, the wire shall continue for at least one extra circumferential turn before being anchored

8.4.5 The clear spacing between the successive turns of the circumferential prestressing wires shall be not less than 6 mm, except at ends or at joints and shall be not more than 50 mm

8.4.6 Test Cube Conversion Factors

The core concrete compressive strength shall be taken on 150 mm \times 150 mm cubes Where the process of manufacture is such that the strength of concrete in the pipe differs from that given by tests on vibrated cubes, the two may be related by suitable conversion factors. If the purchaser requires evidence of these factors, he shall ask for it, before placing the order. The core concrete strength shall be obtained by multiplying the cube strength with the conversion factor and shall be used for design purpose

8.5 Cover Coating

8.5.1 The circumferential prestressing wires on the core pipes shall be protected with a layer of rich cement mortar or concrete or any other approved material which prevents corrosion of wire

8.5.2 If cement mortar is used for cover coating, it shall be applied by rotary brushes or by other approved methods and shall preferably be applied within 16 hours after the prestressing wire is wound The cement, sand and water shall be thoroughly mixed, before being fed into the cover coating machine Minimum cement content in coating mortar shall be 540 kg/m³ and that for concrete 500 kg/m³ Water cement ratio in the mix shall not be less than 0 27, if cement mortar is used for coating Rebound or droppings not exceeding one tourth of the total mass of mix, may be used but the resulting mix proportions shall not be, leaner than original design mix Rebound not used within one hour, shall be discarded

8.5.3 Pneumatic process in which mixing of ingredients is carried out at the nozzle or gun, shall not be permitted

8.5.4 The compressive strength of the cover coating mortar shall be obtained from cubes having area of face 50 cm² or the compressive strength of the cover coating concrete shall be obtained from cube having area of face 100 cm² and shall not be less than 35 N/mm^2 at the time of factory testing of pipe

8.5.5 The mortar coating shall have a minimum cover of 18 mm and concrete coating shall have a minimum cover of 25 mm, over all steel, except at end face and the spigot portion going inside socket, where it will be not less than 15 mm To achieve adequate bond between core and coat, approved bonding agent shall be applied, at ends of pipe for a width of 100 mm, along the circumference to prevent separation between core and coat, at ends

Concurrently with the mortar coating, a cement slurry shall be applied on to the core at a rate of not less than 0.5 l/m^2 just ahead of the mortar coating The slurry shall consist of 1.2 kg of cement to per litre of water

8.5.6 The thickness shall be checked for every pipe as soon as, coating is done

8.5.7 Mortar Soundness

After the mortar coating is cured and prior to transport, the coating on each pipe shall be checked for delamination and hollows by tapping the exterior with a hammer having a head mass of not more than 0.5 kg Any hollows or drumming areas detected by sounding shall be repaired by approved methods

8.5.8 All cement coming in contact with each other shall be of same type and composition and shall be from the same cement works

9 ADDITIONAL REQUIREMENTS FOR CYLINDER PIPES

9.1 The prestressed concrete cylinder pipes shall be manufactured to comply with the following additional requirements

9.1.1 Steel Socket and Spigot Rings

Each ring shall be formed by one piece of steel or a number of pieces of steel butt-welded together. The rings shall be expanded beyond their elastic limit so that they are accurately shaped. The portion of the socket and spigot rings which shall be exposed after the pipe is completed shall be smooth to prevent cutting of the rubber gasket during jointing and shall be protected from corrosion by a sprayed zinc coating of minimum thickness of 0.05 mm followed by one coat of bituminous paint. Other suitable protection may be used with the approval of the purchaser.

9.1.2 Fabrication of Steel Cylinders

The cylinder shall be accurately shaped to the size required and steel socket and spigot rings welded thereto after being jigged square with the longitudinal axis (except for bevel)

9.1.2.1 Testing

Before it is subjected to any further manufacturing process, each steel cylinder, with steel and spigot rings welded on, shall be subjected to water pressure which stresses the steel to at least 140 N/mm², but not more than 175 N/mm² While under stress, the assembly especially welds, shall be inspected and any parts showing leakage shall be repaired and the whole assembly retested

10 SPECIALS

10.1 Fabrication

The steel for fabricated steel plate specials, is cut, shaped and welded so that the finished special has the required shape and internal dimensions. Adjacent segments are jointed by butt welding Before lining and coating, the welding of specials shall be tested by use of hot oil or dye penetrant according to IS 3658 and defects, if any shall be rectified. The steel plate thickness for specials shall be as given in IS 1916

In die penetration test, a white wash is applied over the weld on one side of the cylinder, on other side when coloured paraffin or similar product is applied over the weld, no coloured spot shall appear on the whitewash before 4 h If any coloured spots appear before 4 h, weld shall be repaired and retested

10.2 Lining and Coating

Steel plate specials are lined and coated with concrete or cement mortar or other approved materials, as agreed between the manufacturer and the purchaser The proportion of cement to total aggregate shall not be leaner than 1 3 by mass

10.3 Reinforcement

For concrete or cement mortar coating, reinforcement shall be suitably tack welded to the shell. The reinforcement shall be wire rods and spirals or wire mesh or wire fabric.

10.4 Jointing Between Special and Pipe

The special shall be jointed to the pipe by same rubber ring joint as for pipes or by caulking with mortar For this purpose steel collars shall be welded to steel specials to allow caulking of joint with mortar This is allowed only upto working pressure of 3 kg/cm²

11 JOINTS

11.1 Unless specified otherwise, joints between pipes shall be of the spigot and socket type, so manufactured, that when fitted with the correct size rubber sealing ring, the joint shall be self centreing, flexible and water tight The joint shall be roll-on or confined type Sockets of the pipes may be projecting or flush with the barrel Joint design shall be furnished by manufacturer before undertaking manufacture. The rubber ring joint design, shall take into consideration the tolerance for rubber chord, tolerance for socket and spigot diameters, allowable deflection at joint and permanent set in the rubber ring

11.2 The sealing rings shall be of such size that when jointed, in accordance with the manufacturer's instructions, it shall provide a positive seal within the manufacturer's recommended range of maximum joint deflection Not more than two splices in each ring shall be permitted

12 WORKMANSHIP AND FINISH

12.1 Deviation from the Straightness

When measured by means of a one metre straight edge the deviation from straight per metre length shall not exceed 5 mm

12.2 Finish

Pipe shall be free from local depressions or bulges greater than 5 mm extending over a length, in any direction, greater than twice the thickness of barrel The external surface of the pipe may be sand faced, when coating of cement mortar is applied

13 TEST

13.1 Design Proving and Manufacturing Process Approval Test in Factory

As soon as 4 to 5 pipes are made, these shall be installed and site pressure test shall be conducted, to prove and finalize pipe and joint design and joint dimension tolerances, etc. For one diameter and different pressure, only the test for highest pressure shall be done For this test no external load shall applied

13.2 Hydrostatic Factory Test

The pipe shall be tested in accordance with IS 3597 The pipe must not show leakage Damp or wet patches shall be accepted If the pipe fails to pass the test, it can be cured or repaired to improve its water tightness and then retested In case the pipe does not stand the rated internal pressure, it shall be accepted for lower pressure, purchaser at his own discretion may accept the pipes for lower pressure to which it withstands, provided all other requirements are conforming to this standard

Non-pressure pipes for drainage, sewerage and culverts, shall be tested for 0 14 N/mm²

IS 784 : 2001

13.3 Permeability Test on Coating

The drop of water level, in the specimens of pipes selected, when tested according to the method described in IS 3597 shall not exceed 2 cm³ at the end of two hours and the final permeability between fourth and fifth hour shall not exceed 0 3 cm³ When a higher result is obtained, the test shall be repeated on twice the number of pipes originally tested and the lot shall be accepted, if all pipes pass the test Where retest is not satisfactory, all pipes from that lot may be tested individually and only those with satisfactory results shall be alcoved on the pipe before permeability test is done

The criteria for acceptance is the final permeability The test shall be done immediately after the hydrostatic factory test In case this is done later, the pipe shall be kept wet for 48 hours prior to test

13.4 Three Edge Bearing Test (for Pipes for Drainage, Sewerage and Culverts)

Pipes designed for drainage, sewerage and culverts when subjected to three edge bearing test in accordance with IS 3597 shall meet the requirement as given in Table 2

13.5 Dimensional Characteristic

The pipe selected shall be checked for conformity to the dimensional requirements as given below

- a) Socket and spigot diameters of the pipes as given by manufacturer
- b) Dimensional requirements as given in 5

13.6 Repair of Core and Coat

Pipes not satisfying any of the tests, which may be arising due to occasional imperfection in manufacture or damages during handling, may be treated / repaired and shall be accepted if they satisfy the tests The curing of the repaired concrete or mortar may be done using curing compound

14 SAMPLING AND CRITERIA FOR ACCEPTANCE

14.1 Pressure Pipes for Water Supply and Sewerage

Basic requirement, unless the design proving and manufacturing process test in 13.1 is satisfactorily carried out, no acceptance tests shall be undertaken This has to be done for every new diameter of pipe and for one pressure

All the pipes manufactured under relatively similar conditions in respect of raw-materials and processing operation, shall be grouped together to constitute a lot

Each lot shall be taken separately for sampling and evaluation, for conformity to the requirements of this standard, if the conditions mentioned in 5.1, 5.2, 5.3, 11.1, 11.2 and 12.2 are satisfied (even after repairs) Scale of sampling shall be as given in Table 3

14.2 For non pressure pipes for drainage, sewerage and culvert, only permeability test from Table 3 besides dimensions and three edge load bearing test is necessary

Table 2 Thre	e Edge	Bearing	Test	Loads	for	Pipes 1	for	Drainage,	Sewerage	and	Culverts
(Clause 13.4)											

Nominal Internal Dia of Pipe	Np ₂ Class Load to Produce Maximum 0 25 mm Crack	Np ₃ Class Load to Produce Maximum 0 25 mm Crack	Np ₄ Class Load to Produce Maximum 0 25 mm Crack	Nominal Internal Dia of Pipe	Np ₂ Class Load to Produce Maximum 0 25 mm Crack	Np ₃ Class Load to Produce Maximum 0 25 mm Crack	Np ₄ Class Load to Produce Maximum 0 25 mm Crack
mm	kN/m	kN/m	kN/m	mm	kN/m	kN/m	kN/m
(1)	(2)	(3)	(4)	(1)	(2)	(3)	(4)
200	11 77	14 50	24 60	1 300	28 20	62 30	96 20
250	12 55	15 00	25 50	1 400	29 42	67 06	104 20
300	13 48	15 50	26 40	1 500	30 77	71 85	111 90
350	14 46	16 77	29 80	1 600	32 12	76 64	119 60
400	15 45	19 16	33 90	1 700	33 59	81 40	127 40
450	16 18	21 56	36 90	1 800	35 06	86 22	135 30
500	17 16	23 95	40 00	1 900	36 41	91 00	135 30
600	18 88	28 74	46 30	2 000	37 76	95 80	135 30
700	20 35	33 53	52 20	2 100	38 99	100 60	138 70
800	21 57	38 32	59 30	2 200	40 21	105 38	142 20
900	22 80	43 11	66 30	2 300		110 00	148 60
1 000	24 27	47 90	72 60	2 400		114 96	155 00
1 100	25 50	52 69	80 40	2 500		119 70	160 80
1 200	26 97	57 48	88 30				

Table 3 Scale	of Sampling	and Number	of Accepta	ble De	efective Tests
---------------	-------------	------------	------------	--------	----------------

(Clause	14	1)
---------	----	----

Number of Pipes in Lot	Hydrostatic Test		Socket and Spigot Dimension		Permeability		Coating Thickness		Dimensional Test		Three Edge Bearing Test Drainage, Sewerage, Culvert Pipes	
		**	-	**		**		~ <u>.</u>		**		**
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)	an	(12)	(13)
20 50	All	Nil	All	Nil	3	Nil	3	Nil	່ງ໌	Nil	2	Nil
51 100	All	Nil	All	Nil	5	Nil	5	Nil	5	Nil	2	Nil
101 300	All	Nil	All	Nil	8	Nil	8	Nil	8	Nil	3	Nil
301 500	All	Nil	All	Nil	13	Nil	13	Nil	13	Nit	4	Nil
501 1 000	All	Nil	All	Nil	26	I	26	1	26	1	5	Nil

14.3 After the lot is accepted, each pipe shall be marked with a colour band at ends Different colours to be used for different pressure heads

15 PROCEDURE FOR INSPECTION

15.1 Dimensional Checks

15.1.1 Internal Diameter

The internal diameter shall be measured at each end of the pipe at approximately 50 mm from the ends and at centre Two measurements of the internal diameter at 90° to each other shall be made at each end and at the centre

To accomplish this, 'Go' and 'No Go' gauges of a stiff rod with hardened rounded ends shall be used The length of gauges and colour shall be given below

	Length	Colour	
Gauges fo	or ends		
'Go'	1 mm less than – ve tolerance	Green	
'No Go'	1 mm more than + ve tolerance	Orange	
Gauges fo	or centre		
'Go'	1 mm less than – ve tolerance	Green with white bands	
'No Go'	1 mm more than + ve tolerance	Orange with white bands	

Example

Suppose theoretical diameter of pipe = 1 200 mmand length of pipe 5 m

	Tolera	nce Length of gauge
Ends	± 9	'Go' 1 200 - 8 = 1 192 mm
		'No Go' 1 200 + 10 = 1 210 mm
Centre	± 12	'Go' 1 200 – 11 = 1 189 mm
		'No Go' 1 200 + 13 = 1 213 mm

15.1.2 Core Thickness

Measurement of outer circumference of core shall be made at three barrel positions and average outer diameter of core shall be calculated The inside diameter shall be measured at three barrel positions and average is calculated The core thickness shall be calculated as follows

Average outside diameter - Average inside diameter

15.1.3 Socket and Spigot Diameters

15.1.3.1 Socket diameter (jointing surface)

The socket diameter shall be checked by measuring the sway by touching the two points B and B_1 along the circumference of socket (see Fig 1), BB_1 gives the sway

Example

Suppose the theoretical diameter of socket

	D = 1.383 mm
Permissible variation	= + 2 mm 0 5 mm
The maximum diameter =	$D_1 = 1.385 \text{ mm}$
The minimum diameter =	$D_2 = 1.382.5 \text{ mm}$
The sway = $S = 2 \times [h \times (h \times (h \times (h \times (h \times (h \times (h \times (h$	$D_1 - h)]^{0.5}$
Assume $h = 5 \text{ mm}$ (see Fig.	g 1)
Sway $S = 2 \times [5 \times (138)]$	5 – 5)] ^{0 5}
$= 2 \times 83$	
= 166 mm	
$L^2 = (S/2)^2 + (D_1 - D_2)^2$	- h) ²
$= (166/2)^2 + (1$	385 - 5) ²
= 6 889 + 1 90	4400
I = 1.3825 mm	

This should not be more than the minimum permissible inside diameter



FIG 1 ARRANGEMENT FOR MEASURING SWAY

Therefore, in this case

Length of gauge, L	=	1 382 5 mm
Maximum permissible sway	=	166 mm

15.1.3.2 Spigot Diameter

The gauge as shown in Fig 2 shall be used

Example

Suppose the theoretical outside diameter of spigot = 1 200 mm

Permissible variation = $\pm 1 \text{ mm}$

The maximum diameter = 1 201 mm

The minimum diameter = 1 199 mm

To enable gauge to pass over the spigot surface, the diameter must be more by 1 mm than the maximum spigot diameter

The clearance between gauge points = 1 200 + 1 + 1= 1 202 mm

For checking spigot, the gauge is held in the position as shown in Fig 2. Then by keeping point 'X' fixed, other end 'Y' of gauge is moved over the circumference of spigot, where the gap between spigot surface and gauge is maximum, a strip 2.5 mm, thick and 25 mm wide (straight side) (1.201 - 1.199 = 2.0 mm) is inserted. It should not go Two checks shall be done at 90° to each other

15.1.4 Straightness

The straightness shall be measured by a one metre long gauge The deviation from straight line taken between two points one metre apart, along the pipe barrel shall not exceed 5 mm (see Fig 3)



FIG 3 GAUGE FOR MEASURING STRAIGHTNESS

16 MARKING

16.1 The following information shall be clearly marked on each pipe

- a) Source of identification of the manufacturer,
- b) Size and hydrostatic factory test pressure, and
- c) Date of manufacture

16.2 Each pipe may also be marked with the Standard Mark

16.2.1 The use of the Standard Mark is governed by the provisions of *Bureau of Indian Standards Act*, 1986 and the Rules and Regulations made thereunder The details of conditions under which a licence for the use of Standard Mark may be granted to manufacturer and producers may be obtained from the Bureau of Indian Standards



FIG 2 ARRANGEMENT FOR CHECKING SPIGOT DIAMETER

ANNEX A

(Clause 2)

LIST OF REFERRED INDIAN STANDARDS

IS No	Tıtle	IS No	Tule
432	Specification for mild steel and medium tensile steel bars and hard- drawn steel wire for concrete rein-	1916 1989	Specification for steel cylinder pipe with concrete lining and coating (first revision)
(Part 1) 1982	forcement Part 1 Mild steel and medium tensile	2062 1992	Steel for general structural purposes (fourth revision)
(Part 2) 1982	steel bars (third revision) Part 2 Hard-drawn steel wire (third	3597 1998	Methods of test for concrete pipes (second revision)
455 1989	revision) Specification for Portland slag	3658 1999	Code of practice for liquid perma- nent flaw detection (second revision)
783 1985	cement (fourth revision) Code of practice for laying of	5382 1985	Rubber sealing rings for gas mains, water mains and sewers (first
1566 1987	concrete pipes (first revision) Specification for hard-drawn steel	6003 1983	revision) Specification for intended wire for
1500 1782	wire fabric for concrete reinforce-	0005 1985	prestressed concrete (first revision)
1785	ment (second revision) Specification for plain hard-drawn steel wire for prestressed concrete	6006 1983	Specification for uncoated stress relieved strand for prestressed concrete (first revision)
(Part 1) 1983	Part 1 Cold-drawn stress relieved wire (second revision)	8041 1990	Specification for rapid hardening Portland cement (second revision)
(Part 2) 1983 1786 1985	Part 2 As drawn wire (first revision) Specification for high strength	8112 1989	Specification for 43 grade ordinary Portland cement (<i>first revision</i>)
	deformed steel bars and wires for concrete reinforcement (third	9103 1999	Specification for admixtures for concrete (first revision)
	revision)	12269 1987	Specification for 53 grade ordinary Portland cement

ANNEX B

(Clause 6)

INDICATIVE DIMENSIONS OF SOCKET AND SPIGOT OF PRESTRESSED CONCRETE PIPE

B-1 The indicative dimensions of socket and spigot of prestressed concrete pipe are given below (see also Fig. 4):





CONFINED JOINT



A Nominal Dia of	Roll	On Joint	Confine	ed Joint
Pipe	<i>C</i> Internal Dia of Socket	<i>B</i> External Dia of Spigot	C Internal Dia of Socket	B External Dia of Spigot
200	308	290	308	290
250	352	334	352	334
300	404	386	404	386
350	456	438	456	438
400	518	500	518	500
450	562	544	562	544
500	612	594	612	594
600	726.5	704	726.5	704
700	826.5	804	826.5	804
800	937.5	915	937.5	915
900	1 058.5	1 036	1 058.5	1 036
1 000	1 165.5	1 141	1 165.5	1 141
1 100	1 270.5	1 246	1 270.5	1 246
1 200	1 381.5	1 357	1 381.5	1 337
1 300	1 496.5	1 472	1 496.5	1 472
1 400	1 595.5	1 571	1 595.5	1 571
1 500	1 706	1 678	1 706	1 678
1 600	1818	1 790	1818	1 790
1 700	1 928	1 900	1 928	1 900
1 800	2 036	2 008	2 036	2 008
1 900	2 154	2 126	2 154	2 126
2 000	2 264	2 236	2 264	2 236
2 100	2 374	2 346	2 374	2 346
2 200	2 488	2 454.5	2 488	2 431.5
2 300	2 598	2 564.5	2 598	2 564.5
2 400	2 708	2 674.5	2 708	2 674.5
2 500	2 818	2 784.5	2 818	2 784.5

NOTE -- All the manufacturers shall try to achieve above dimensions within a period of five years.

ANNEX C

(Clause 7 1)

INFORMATION TO BE SUPPLIED BY PURCHASER WITH AN ENQUIRY OR ORDER FOR PRESTRESSED CONCRETE PIPES

- C-1 The following information shall be supplied
 - a) The type of cement to be used in the core and the cover coat (4.1),
 - b) Whether or not a bituminous or other approved coating is required internally and externally (4.8),
 - c) The maximum working pressure (3.4),
 - d) The maximum site test pressure (3.5),
 - e) Factory test pressure (3.6),
 - f) Pressure in addition to (c) to which the pipeline will be subjected due to surge (water hammer) (3.7), if any, and
 - g) Following pipe installation details

- 1) The maximum and minimum depths of cover over the crown of the pipe
- 2) The width of the trench at the crown of the pipe (normally outside diameter of pipe + 600 mm) If the pipes are to be laid above ground in case of partial trench, full details including L-section should be supplied
- 3) Whether more than one pipeline is to be laid in the trench and if so, what will be the trench width at the crown of the pipe
- 4) Details of the backfill material, that is, sand, gravel, etc
- 5) Density of filling material
- 6) Type of bedding intended
- 7) Anticipated superimposed loading on ground surface

ANNEX D

(Clause 7 4 2)

TYPICAL CALCULATION FOR THE DESIGN OF LONGITUDINALS FOR PIPE DIAMETER 600 mm AND BELOW

D-1 Explanation of various symbols used in subsequent clauses is given in Annex K

D-2 DATA

Diameter of pipe, D	= 500 mm
Effective length of pipe	= 5 000 mm
Core thickness, t _c	= 35 mm
Coat thickness, $t_{\rm b}$	= 22 mm

Minimum compressive strength of core concrete (spun) at various stages

- a) Characteristic compressive = 40 N/mm² design strength, f_{ck}
- b) At winding (see 8.4.1), $f_{p2} = 25 \text{ N/mm}^2$
- c) At detensioning = 15 N/mm² longitudinals (see 8.3.2), f_{pl} Diameter of longitudinal wire = 4 mm
- Ultimate tensile strength = 1 715 N/mm² of wire (see 4.5.1)

Initial compressive stress = $10\ 657\ 5\ \text{N/mm}^2$ induced in core, f_{ci} (Assumed)

D-3 CALCULATION OF STRESS IN LONGITUDINAL DIRECTION

D-3.1 Centreline Spacing Between Longitudinal Wires

Centreline spacing between longitudinal wires shall not exceed twice the core thickness or 150 mm whichever is greater (see 8.3), that is

2 × 35 or 150 mm, that is, 150 mm

Number of longitudinals = 16 considered in design

Centreline spacing = $3 \, 141.6 \times (D + T_c)/N$ between longitudinal wires = $3 \, 141.6 \times (500 + 35)/16$,

= 105 04 mm < 150 mm

Hence, number of longitudinals considered in design is correct

D-3.2 Intial Longitudinal Precompression in Core

Initial stress in longitudinal wire (see 8.4.2),
$$f_{\rm sil}$$

1 715 × 0.75 = 1 286.25 N/mm²
Area of core concrete, A_c

 $3.1416 \times 535 \times 35 = 58\ 826.46\ \mathrm{mm^2}$

Longitudinal precompression

$$= \frac{\text{Longitudinal force}}{A_{c}} = \frac{N \times A_{di} \times f_{sil}}{A_{c}}$$

Initial precompression, $f_{cl} = \frac{16 \times 12.57 \times 1286.25}{58\,826.46}$

= 4.397 5 N/mm²

Concrete strength required at detensioning of longitudinals, f_{n} (see 8.3.2)

 $2 \times f_{cl}$ OR 15 N/mm², whichever is greater,

that is, $2 \times 4.3975 = 8.7950$ or 15 N/mm², whichever is greater

Adopt $f_{nl} = 15 \text{ N/mm}^2$

D-3.3 Loss of Stress in Longitudinal Wires (see Annex F)

a) Relaxation of wire

 0.08 × f_{sil} = 0.08 × 1 286.25 = 102.90 N/mm²
 b) Deformation due to creep

$$2.50 \times f_{cil} = 2.50 \times 4.3975 = 10.99 \text{ N/mm}^2$$

- c) Deformation due to shrinkage $0.000 \ 1 \times E_s = 0.000 \ 1 \times 20.0 \times 10^4$ $= 20.00 \ \text{N/mm}^2$
- d) Yield due to mould shortening, wire stretch due to filling, vibration during spinning, etc

$$=\frac{2 \times E_{\rm s}}{\text{Effective length of pipe + 80 mm}}$$

$$=\frac{2 \times 20 \times 10^4}{5\,000 + 80} = 78.74 \,\mathrm{N/mm^2}$$

Total losses = 102.90 + 10.99 + 20.0 + 78.74= 212.63 N/mm^2

D-3.4 Precompression in Core in Longitudinal Direction

At the stage of winding

Loss of prestress in longitudinal wire at winding = Total losses $\times 0.9 = 212.63 \times 0.9 = 191.37 \text{ N/mm}^2$ Stress in longitudinal wire at winding (f_{slw}) = 1 286.25 - 191.37 f_{slw} = 1 094.88 N/mm²

Precompression at
winding,
$$f_{clw} = \frac{16 \times 12.57 \times 1094.88}{58\ 826.46}$$

$$f_{\rm clw} = 3.742 \ 2 \ \rm N/mm^2$$

At site test

Stress in longitudinal wire after losses, $f_{1} = 1.286.25 - 212.63 = 1.073.62 \text{ N/mm}^2$

Final precompression,
$$f_{cl} = \frac{16 \times 12.57 \times 1073.62}{58\ 826.46}$$

 $f_{cl} = 3.670\ 5\ N/mm^2$

D-3.5 Longitudinal Stress Due to Circumferential Winding

Maximum local longitudinal tensile stress during winding

 $= 0.284 \times 10.6575 = 3.0267$ N/mm²

D-3.6 Stress Due to Beam Action

Self weight of pipe $W_s = 2 \ 295.62 \ \text{N/m}$ Weight of water $W_w = 1 \ 963.50 \ \text{N/m}$

Earth load to be considered (see 7.4.1) $2.2 \times (D + 2 \times T_c + 2 \times T_b) = 1 350.80 \text{ N/m}$ $= 2.2 \times 614$

Total load $W = W_s + W_w + 1\ 350.80 = 5\ 609.92\ \text{N/m}$ Modulus of circular section of pipe (Z_i)

$$\frac{3.1416}{32} \times \frac{614^4 - 500^4}{614} = 12\ 731\ 728\ \mathrm{mm}^3$$

$$\frac{WL^2}{8} = \frac{5\,609.92 \times 5 \times 5 \times 1\,000}{8} = 17\,531\,000\,\,\text{Nmm}$$

Stress due to beam action = $\frac{BM}{Z_1}$ = 1.376 9 N / mm²

D-3.7 Stress Due to Self Weight of Core

Self weight of core $(W_{a}) = 1.411.84$ N/m

Modulus of circular section of core (Z_2)

$$\frac{3.1416}{32} \times \frac{570^4 - 500^4}{570} = 7\,416\,520\,\,\mathrm{mm^3}$$

B.M. due to mass of core (BM)

$$\frac{1\,411.84\times5\times5\times1\,000}{8} = 4\,411\,985\,\text{Nmm}$$

Stress due to self weight of core = $\frac{BM}{Z_2}$ = ±0.594 9 N/mm²

D-3.8 Stress Due to Transport and Handling

Bending moment = 844×10^7 (see Note 3 under 7.4.1)

Modulus of circular section of pipe (Z_1)

$$\frac{31416}{32} \times \frac{614^4 - 500^4}{614} = 12\ 731\ 728\ \mathrm{mm}^3$$

Stress due to transport and handling =

$$\frac{\text{Bending Moment}}{Z_1} = \frac{844 \times 10^7}{12\ 731\ 728} = \pm\ 6\ 629\ 1\ \text{N}\ /\ \text{mm}^2$$

D-3.9 Summary of Stresses in Longitudinal Direction

Stresses due to	Compressive N/mm ²	Tensile N/mm ²
Maximum local longitudinal tensile stress due to ben- ding during winding		-3 026 7
Beam action	+ 1 376 9	-1 376 9
Self weight of core	+ 0 594 9	-0 594 9
Transport and unloading	+ 6 629 1	-6 629 1
Initial precompression	+ 4 397 5	
Precompression at winding	+ 3 743 2	
Final precompression	+ 3 670 5	

D-3.10 Load Combination of Longitudinal Stresses Under Different Condition (see 7.4.1)

Actual against Permissible

Loading Combination	Longitudinal Stresses N/mm ²				
	Tens	sile	Compressive		
	Actual	Permissible	Actual	Permissible	
a) Longitudinal prestress in barrel (after losses)			+3 6705	Minimum residual compressive stress +2 5	
b) Longitudinal prestress during	- (3 026 7 + 0 594 9) + 3 743 2 = +0 121 6	$056 \times (f_{p2})^{05} 056 \times (25)^{05} = -28000$	(0 594 9 + 3 743 2) = + 4 338 1	$0 5 \times (f_{p2})^{05} \times 25 = 12 500 0$	
winding	+0.121 6 <	-2.800 0	+4.338 1 < 12.500 0		
c) Longitudinal prestress after	(-1 376 9 + 3 670 5) = +2 293 6	$0 34 \times (f_{ck})^{05} 0 34 \times (40)^{05} = -2 150 3$	(1 376 9 + 3 670 5) = + 5 047 4	$0.5 \times (f_{ck})^{0.5} \times 40$ = 20.0	
losses plus beam action	es plus beam +2.293 6 < - 2.150 3		+5.047 4 < 20.0		
d) Handling before winding	(-0 594 9 + 3 743 2) = +3 148 3	- 0 67	(0 594 9 + 3 743 2) = + 4 338 1	$0.5 \times (f_{p1})^{0.5} \times 15$ = 7.5	
	+3.148 3	<-0.67	+ 4.338	1 < 7.5	
e) Transport and unloading	-6 629 1 + 3 670 5 = -2 958 6	$056 \times (f_{ck})^{05} 056 \times (40)^{05} = -35417$	+6 629 1 + 3 670 5 = +10 299 6	$05 \times (f_{ck})^{05} \times 40$ = 20	
	-2.958 6 <	- 3.541 7	+10.299	6 < 20.0	

ANNEX E

(Clause 7.4.3)

THRUST AND MOMENT COEFFICIENTS

E-1 The coefficients at control sections for bedding angles from 30° to 180° developed by use of Olander's Equations are as given below



Bedding Location of		Thri	ist Coefficients	ς, C _ι	Mom	ent Coefficient,	C _m
Angle	Section θ	Pipe C _{tp}	Water C_{tw}	Earth C_{te}	Pipe C _{tp}	Water C_{tw}	Earth C_{te}
	0°	0 078	-0 237	+0 487	+0 079	+0 079	+0 062
30°	104°	+0 302	-0 058	+0 633	+0 100	+0 100	+0 085
	180°	+0 125	-0 352	+0 376	+0 194	+0 194	+0 173
	0°	-0 071	0 230	+0 425	+0 076	+0 076	+0 065
60°	104°	+0 302	-0 059	+0 576	+0 096	+0 096	+0 086
	180°	+0 168	-0 310	+0 345	+0 155	+0 155	+0 145
	0°	0 061	0 220	+0 382	+0 070	+0 070	+0 069
90°	104°	+0 295	-0 062	+0 539	+0 088	+0 088	+0 089
	180°	+0 207	-0 270	+0 326	+0 121	+0 121	+0 125
	0°	-0 046	-0 205	+0 351	+0 063	+0 063	+0 073
120°	100°	+0 282	-0 065	+0 516	+0 077	+0 077	+0 091
	180°	+0 245	0 233	+0 316	+0 091	+0 091	+0 109
	0°	-0 026	0 185	+0 331	+0 054	+0 054	+0 079
150°	96°	+0 267	-0 067	+0 504	+0 063	+0 063	+0 094
	180°	+0 282	-0 196	+0 313	+0 065	+0 065	+0 097
	0°	-0 000	-0 159	+0 318	+0 044	+0 044	+0 087
180°	90°	+0 250	-0 068	+0 500	+0 047	+0 047	+0 095
	180°	+0 318	0 159	+0 318	+0 044	+0 044	+0 087

ANNEX F

(Clauses 7 5, G-3 and J-4 2 2 1)

LOSS OF PRESTRESS

F-1 Explanation of various symbols used in subsequent clause is given in Annex K

F-2 CALCULATION FOR LOSS OF PRESTRESS

SI		Longitudinal	Cırcum-
No	1	(Pre Tensioning)	ferential
			(Post
			Tensioning)
ł	Elastic deformation		$32f_{c1}$
2	Relaxation of wire	$0.16 f_{st long}$	$0.16f_{s_1}$
3	Deformation due to creep	$2.5 f_{si long}$	$25f_{s1}$
4	Deformation due to shrinkage	0 000 1 E _s	0 000 1 E _s
5	Yield due to mould shortening (wire strett due to filling, vibration during spinning, etc slippage = 2 mm)	$\frac{ch}{s} \frac{2E_s}{L+80}$	

where

- f_{clong} = Initial stress in core in longitudinal direction in N/mm²
- f_{ci} = Initial stress in core in circumferential direction in N/mm²
- f_{stiong} = Initial stress in core in circumferential wire in N/mm²
- E = Modulus of elasticity of high tensile wire
 - = $2.00 \times 10^5 \text{ N/mm}^2$ (for stress relieved), and
 - = 1.93×10^5 N/mm² (for as drawn)
- L = Effective length of pipc in mm + 80 mm

NOTE --- Loss of stress in high tensile wire at factory test pressure will be 90 percent of the total losses

ANNEX G

(Clauses 7 6, H-3 3 and J-5)

TYPICAL DESIGN OF PRESTRESSED CONCRE FE PIPE OF DIA 1 200 mm — WINDING BY PROCESS OF COUNTER WEIGHT/BREAK

G-1 Fxplanation of various symb quent clauses is given in Annex K	ols used in subse-	Process for winding	Counter Weight/ Break
		Core thickness, T_{c}	= 70 mm
G-2 DATA		Coat thickness, $T_{\rm b}$	= 22 mm
Diameter of pipe, D	= 1 200 mm	Width of trench	= 1984 m
Effective length of pipe, L	= 50 m	$(D + 2T_{\rm c} + 2T_{\rm b} + 600), B_{\rm t}$	
Working pressure, Pw (see 3.4)	$= 0.700 \text{ N/mm}^2$	Diameter of circumferential	= 4 mm
Site test pressure, P.	$= 1.050 \text{ N/mm}^2$	wire, d_s	
Factory test pressure, P,	$= 1 150 \text{ N/mm}^2$	Diameter of longitudinal	= 4 mm
Height of fill, H	= 100 m	wire, d_c	
Density of fill material, K	$= 15700 \text{ N/m}^3$	Number of longitudinals, N	= 28
Live load	Class AA (IRC)	Ultimate tensile strength of circumferential wire (see 4.5	$= 1.715 \text{ N/mm}^2$ 5.1)
G-3 ASSUMPTIONS		Ultimate tensile strength of	$= 1.715 \text{ N/mm}^2$
Density of core concrete, K_c	$= 24\ 000\ \text{N/m}^3$	longitudinal wire (see 4.5.1))
Density of coating, $K_{\rm b}$	$= 21 600 \text{ N/m}^3$	Area of circumferential wire, A	$= 0.623 \text{mm}^2/\text{mm}$
Density of water, K_w	$= 10\ 000\ \text{N/m}^3$	Modulus of elasticity of steel, E_s	$= 20 \times 10^4 \text{N/mm}^2$

Modulus of elasticity of $= 4 \times 10^4 \text{ N/mm}^2$ concrete, E_c = 5

Minimum compressive strength of core concrete (spun) at various stages

- a) Characteristic compressive = 40 N/mm² design strength, f_{ak}
- b) At winding, f_{n} , (see 8.4.1) = 25 N/mm²
- c) At detensioning longitudinals f_{rl} (see 8.3.2)

G-4 CALCULATION OF PRESTRESS IN CORE IN CIRCUMFERENTIAL DIRECTION

G-4.1 Spacing of Circumferential Wire

Allowable clear spacing (see 8.4.5) Maximum clear spacing of wire = 50 mm Minimum clear spacing of wire = 6 mm Area of spiral considered in = 0 623 N/mm² design (A_a) Number of turns per meter length = 0 623 × $\frac{1000}{0.7854}$ × (4)² = 49 57 Centre to centre spacing of spiral wire = $\frac{1000}{4957}$ = 20 17 mm Clear spacing of spiral = 16 17 mm

wire is 20 17- 4

16 17 mm is in between 50 mm and 6 mm Hence, the area of spiral (A_i) considered is correct Initial stress in wire during winding (f_{si}) (see 8.4.2) 0 75 × 1 715 = 1 286 25N/mm²

G-4.2 Initial Compressive Stress Induced in Core (f_{ci})

 $= 1\ 286\ 25 \times \frac{0\ 623}{70} = 11\ 447\ 6\ \text{N/mm}^2$

G-4.3 Loss of Stress in Wire (see Annex E)

- a) Elastic deformation
- $3 \ 2 \times f_{c_1} = 3 \ 2 \times 11 \ 447 \ 6 = 36 \ 63 \ N/mm^2$ b) Relaxation of wire
- $0.08 \times f_{s1} = 0.08 \times 1.286.25 = 102.90 \text{ N/mm}^2$
- c) Deformation due to creep $2.5 \times 11.447.6 = 28.62 \text{ N/mm}^2$
- d) Deformation due to shrinkage $0\ 000\ 1 \times E_s = 0\ 000\ 1 \times 20 \times 10^4 = 20\ 00\ \text{N/mm}^2$ Total losses

36 63 + 102 90 + 28 62 + 20 00 = 188 15 N/mm²

Losses at factory test

$$0.9 \times \text{Total loss}$$

 $0.9 \times 188 15 = 169.34 \text{ N/mm}^2$
Stress in wire at factory test, (f_{sf})
 $= 1.286.25 - 169.34 = 1.116.91 \text{ N/mm}^2$
Stress in wire at site test (f_s)
 $= 1.286.25 - 188.15 = 1.098.10 \text{ N/mm}^2$

G-4.4 Compressive Stress Induced in Core at Factory Test

$$f_{\rm cf} = 1\,116\,91 \times \frac{0\,623}{70} f_{\rm cf} = +\,9\,940\,5\,\,{\rm N/mm^2}$$

G-4.4.1 Compressive Stress in Core at Site Test

$$f_{\rm ct} = 1\ 098\ 10 \times \frac{0\ 623}{70}\ f_{\rm ct} = +\ 9\ 773\ 1\ \rm N/mm^2$$

G-4.5 Section Constant

- a) Outside diameter of core (ODC) ODC = D + 2 × T_c = 1 340 mm
 b) Outside diameter of pipe (ODP)
- $ODP = D + 2 \times T_c + 2 \times T_b = 1 384 \text{ mm}$
- c) Mean radius of pipe (r)

$$=\frac{D+T_{\rm c}+T_{\rm b}}{2} = 646 \,\mathrm{mm}$$

- d) Modulus of section for circumferential stress (Z) $Z = \frac{1}{4} \times (T_c + T_b)^2 \times 1000 = 1410667 \text{mm}^3/\text{m}$
- e) Sectional area (A) $A = (T_c + T_b) \times 1000 = 92000 \text{ mm}^2$
- f) Modulus of circular section of core (Z_2)

$$\frac{31416}{32} \times \frac{\text{ODP}^4 - \text{D}^4}{\text{ODC}} = 84\,297\,111\,\text{mm}^3$$

g) Modulus of circular section of pipe (Z_1)

$$\frac{31416}{32} \times \frac{\text{ODP}^4 - \text{D}^4}{\text{ODP}} = 113\ 168\ 797\ \text{mm}^3$$

G-4.6 Self Weight of Pipe (W.)

a) Self weight of core (W_c) $W_c = 3 \ 141 \ 6 \times (D + T_c) \times T_c \times K_c$ $= 3 \ 141 \ 6 \times (1 \ 200 + 0 \ 070) \times 0.070 \times 24 \ 000$ $= 6 \ 702 \ 92 \ N/m$ b) Self weight of coat (W_b) $W_b = 3 \ 141 \ 6 \times (D + 2 \times T_c + T_b) \times T_b \times K_b$

= $3 141 6 \times (1 200 + 2 \times 0 070 + 0 022)$ $\times 0 022 \times 21 600$ = 2 033 31N/m

- c) Self weight of pipe (W_s) $W_s = W_c + W_b = 873623 \text{ N/m}$
- G-4.7 Weight of Water (W_)

 $W_{\rm w} = (3\ 141\ 6/4) \times D^2 \times K_{\rm w}$ = 0 7 85 4 × (1 200)² × 10 000 = 11 309 76 N/m

G-4.8 Weight Of Earth Fill (W,) (see Fig 4 of IS 783)

 $\frac{H}{B_{t}} = \frac{100}{1984} = 0\ 5040$ $C_{t} = 0\ 472\ 3$ $W_{e} = (C_{t} \times K_{e} \times B_{t}^{2})$ $= 0\ 472\ 3 \times 15\ 700 \times (1\ 984)^{2}$ $W_{e} = 29\ 187\ 77\ \text{N/m}$

G-4.9 Live Load (W) (see 10.1)

$$W_1 = C_n \times P/l \times O$$

where

P = Axle load = 61 300 N O = Impact factor = 1 0 l = 1 15 H + 2 ODP + S = 3 918

Assuming S = 0

the value of $C_p = 0.664$ is obtained from Fig. 3 of IS 783, using the values,

for ratio
$$\frac{l}{2H} = \frac{3918}{2 \times 1} = 1959$$
, and
 $\frac{D}{2H} = \frac{1384}{2 \times 1} = 0.692$
 $W_1 = \frac{0.664 \times 613.001}{3.918}$ $W_1 = 10.388.80$ N/m

G-4.10 Calculations of Stresses Due to External Loads

Circumferential stresses due to external load Olander's (coefficient for 90° bedding angle)

External	At Bo	ttom
Load	$\overline{\text{Moment}(M_{\rm h})}$	Thrust (H _k)
Self weight	+ 0 121 W, r	+ 0 207 W
Water weight	+ 0 121 <i>W</i> _r	– 0 270 W
Earth fill	+ 0 125 W r	+ 0 326 W
Live load	+ 0 125 $W_{1}r$	$+0.326 W_{1}$

+ Moment causes tension inside pipe at bottom

Only stresses at bottom are calculated as those are more severe

G-4.10.1 Stress Due to Self Weight of Pipe

Moment (M) = $0 \ 121 \times 8 \ 736 \ 23 \times 646 \ 0$ = $682 \ 876 \ 20 \ Nmm$

Thrust (T) $= 0.207 \times 8.736.23$ = 1 808 40 N/m Stress due to moment $\frac{M}{Z} = \frac{68287620}{1410667} = 04841 \text{ N/mm}^2$ Stress due to thrust $\frac{T}{A} = \frac{180840}{92000}$ $= 0.0197 \text{ N/mm}^2$ Net tensile stress = (-0.4841) + (+0.0197) $= -0.464 \text{ } \text{ N/mm}^2$ Net compressive stress $= (+0.484 1) + (+0.019 7) = +0.503 8 N/mm^{2}$ G-4.10.2 Stress Due to Weight of Water Moment (M) = 0 121 × 11 309 76 × 646 0 = 884 038 70 Nmm = 0 270 × 11 309 8 Thrust (T) = 3 053 64 N/m Stress due to moment $\frac{M}{Z} = \frac{884\ 038\ 70}{1\ 410\ 667} = 0\ 626\ 7\ \text{N/mm}^2$ Stress due to thrust $\frac{T}{T} = \frac{305364}{1000}$ $= 0.033 2 \text{ N/mm}^2$ 92 000 Net tensile stress $= (-0.626.7) + (-0.033.2) = -0.659.9 \text{ N/mm}^2$ Net compressive stress $= (+0.626.7) + (-0.033.2) = +0.593.5 \text{ N/mm}^2$ G-4.10.3 Stress Due to Weight of Earth Fill Moment (M) $= 0.125 \times 29.187.77 \times 646.0$ = 2 356 912 40 Nmm = 0 326 × 29 187 77 Thrust (T) = 9 515 21 N/m Stress due to moment $\frac{M}{Z} = \frac{2\,356\,912\,40}{1\,410\,667} = 1\,670\,8\,\mathrm{N/mm^2}$ Stress due to thrust $= 0.103 4 \text{ N/mm}^2$ 92 000 Net tensile stress $= (-1\ 670\ 8) + (+0\ 103\ 4) = -1\ 567\ 4\ N/mm^2$ Net compressive stress $= (+1\ 670\ 8) + (+0\ 103\ 4) = +1\ 774\ 2\ N/mm^{2}$ G-4.10.4 Stress Due to Live Load

Moment (M) = $0.125 \times 10.388.8 \times 646.0$ = 838.895.60 Nmm

Thrust (7) =
$$0.326 \times 10.388.8$$

= $3.386.75$ N/m

Stress due to moment

$$\frac{M}{Z} = \frac{838\,895\,60}{1\,410\,\,667} = 0\,594\,7\,\,\text{N/mm}^2$$

Stress due to thrust

$$\frac{T}{A} = \frac{3\,886\,75}{92\,000} = 0\,036\,8\,\,\text{N/mm}^2$$

Net tensile stress

 $= (-05947) + (+00368) = -05579 \text{ N/mm}^2$ Net compressive stress

 $= (+0.594.7) + (+0.036.8) = +0.631.5 \text{ N/mm}^2$

G-4.11 Calculation of Stresses in Pipe Core Due to Internal Pressure

a) At factory test

$$f_{wf} = \frac{-P_{t} \times D}{2 \times [T_{c} + (n \times A_{s})]}$$
$$= \frac{-1150 \times 1200}{2 \times [70 + (5 \times 0.623)]}$$
$$f_{wf} = -9.437.2 \text{ N/mm}^{2}$$

b) At site test

$$f_{ws} = \frac{-P_{s} \times D}{2 \times \left[T_{c} + \left(n \times A_{s}\right)\right]}$$

$$= \frac{-1150 \times 1200}{2 \times [70 + (5 \times 0.623)]}$$

f_{ws} = -8.616.6 N/mm²

c) At working pressure

$$f_{ww} = \frac{-P_w \times D}{2 \times [T_c + (n \times A_s)]}$$
$$= \frac{-0.700 \times 1200}{2 \times [70 + (5 \times 0.623)]}$$
$$f_{ww} = -5.744 \text{ A N/mm}^2$$

G-4.12 Summary of Circumferential Stresses

Stresses Due To	<i>Tensıle</i> N/mm ²	Compressive N/mm ²
a) External Loads		
Self weight of pipe	- 0 464 4	+ 0 503 8
Weight of water	- 0 659 9	+ 0 593 5
Weight of earth fill	- 1 567 4	+ 1 774 2
Live load	- 0 557 9	+ 0 631 5
b) Internal Pressure		
Site test pressure	- 8 616 6	
Working pressure	- 5 744 4	
Factory test pressure	- 9 437 2	
c) Compressvie Stress in (Core Due to	Circumferen-
tial		Winding
Initial compressive stres	ss	+11 447 6
Prestress at factory test		+ 9 940 5
Prestress at site test		+ 9 773 1

G-5 CIRCUMFERENTIAL PRESTRESS REQUIREMENTS (see 7.4.3)

Loading Combination		Circumferential Stresses in N/mm ²				
		Tensile	Com	pressive		
	Actual	Permissible	Actual	Permissible		
a) Circumferential			(0 503 8 +	$0.55 \times f_{n^2}$		
pre-stressing			11 447 6)	0 55 × 25		
condition			= 11 951 4	= 13 750 0		
Self weight + Initial prestress			+ 11.951 4 <	13.750 0		
b) Site test condition	10 464 4	0 12 (6)0 67	(0.503.8.1	0.46 4.6		
(Sell weight +	-(04044+	$(13)(V_{ck})$		$0.43 \times J_{ck}$		
Forth fill load +	15474	$= 0.13 \times (40)$	1 774 2 +	= 0 45 × 40		
Sute test press	9 6 1 6 6 1 4 7	1 34	0 772 1)	- 180		
Site test press	0 772 1		9 / / 3 I J - + 12 644 6			
rmai prestress)	-135 5 2		- +12 044 0			
	- 1.535 2 <	-1.54	+ 12.644 6 <	18.0		

Combination							
		Tensile		Compressive			
	Actual		Permissible	Actual		Permissible	
c) Factory test condition							
(Self weight +	-(0 464 4 +			(0 503 8 +		$0.45 \times f_{ck}$	
Weight of water +	0 659 9 +			ò 593 5 +		$= 0.45 \times 40$	
Factory test	9 437 2) +		0 13 (fck) ^{0 67}	9 940 5)		= 18 0	
pressure +	9 940 5		$0.13 \times (40)^{0.67}$	= + 110378			
Prestress at factory	=0 6210		= -1 54				
test)	- 0.621 0	<	-1.54	+11.037 8	<	18.0	
d) Operating condition							
(Self weight +	(0 464 4 +		0 00	(0 503 8 +		$0.45 \times f_{ck}$	
Weight of water +	0 659 9 +			0 593 5 +		$= 0.45 \times 40$	
Earth fill load +	1 567 4 +			1 774 2 +		=18 0	
Working pressure	5 744 4) +			9 731)			
final prestress)	9 773 1			= +12 644 6			
	- +1 337 0						
	+ 1.337 0	<	0.00	+12.644 6	<	18.0	
e) Live load condition						$0.45 \times f_{ik}$	
[Operating	(+1 337 0) +		$0.13 (f_{ck})^{0.67}$	(+12 644 6) +		$= 0.45 \times 40$	
condition live load	(0 557 9)		$0.13 \times (40)^{0.67}$	(+0 631 5)		= 180	
(with impact)]	= +0 779 1		= -1 54	= +13 276 1			
	+0.779 1	<	-1.54	+13.276 1	<	18.0	
$(f_{ck} = 40 \text{ N/mm}^2, f_{p2})$	$= 25 \text{ N/mm}^2$),	- v	e is tensile, + ve i	s compressive			

G-6 CALCULATION OF STRESS IN LONGI-TUDINAL DIRECTION

Loading

G-6.1 Centreline Spacing Between Longitudinal Wires (see 8.3)

Centreline spacing between longitudinal wires shall not exceed twice the core thickness or 150 mm whichever is greater, that is

2 × 70 or 150 mm	150 mm
Number of longitudinals	= 28
considered in design	
Centreline spacing between	$3146 \times (D + T)$

Centreline spacing between
$$= \frac{3146 \times (D + T_c)}{N}$$

$$=\frac{31416\times(1200+70)}{28}$$
, that is 142.49 mm

142 49 mm < 150 mm

Hence, number of longitudinals considered in design is correct

G-6.2 Initial Longitudinal Precompression in Core (see 8.4.2)

Initial stress in longitudinal wire
$$(f_{sil})$$

1 715 0 × 0 75 = 1 286 25 N/mm²

Area of core concrete (A_c)

Circumferential Stresses in N/mm²

 $3 141 6 \times 1 270 \times 70 = 279 288 24 \text{ mm}^2$

Longitudinal precompression

$$= \frac{\text{Longitudinal precompression}}{A_{c}} = \frac{N \times A_{dl} \times f_{ul}}{A_{c}}$$

Initial precompression
$$(f_{cil}) = \frac{28 \times 1257 \times 128625}{27928824}$$

= 1 620 9 N/mm²

Concrete strength required at detensioning of longitudinals (f_{pl}) (see 8.3.2)

 $2 \times f_{cut}$ or 15 N/mm², whichever is greater

that is $2 \times 16209 = 324$ or 15 N/mm^2 , whichever is greater

Adopt $f_{p1} = 15 \text{ N/mm}^2$

G-6.3 Loss of Stress in Longitudinal Wires (see Annex F)

a) Relaxation of wire

$$0.08 \times f_{sul} = 0.08 \times 1.286.25 = 102.9 \text{ N/mm}^2$$

- b) Deformation due to creep = $250 \times f_{cil} = 250 \times 16209 = 405 \text{ N/mm}^2$
- c) Deformation due to shrinkage
 - $= 0\ 000\ 1 \times E_{\rm s}$ = 0 000 1 × 20 0 × 10⁴
 - = 20 00 N/mm²
- d) Yield due to mould shortening (Wire stretch due to filling, vibration during spinning, etc)

$$= \frac{2 \times E_s}{\text{Effective length of pipe + 80 mm}}$$

$$= \frac{2 \times 20 \times 10}{5\ 000 + 80} = 78\ 74\ \text{N/mm}^2$$

Total losses = 102 9 + 4 05 + 20 0 + 78 74

= 205 69 N/mm²

G-6.4 Precompression in Core in Longitudinal Direction

At the stage of winding

Loss of prestress in longi-	= Total loss × 0 9
tudinal wire at winding	$= 20569 \times 09$
	$= 185 12 \text{ N/mm}^2$
Stress in longitudinal wire	= 1 286 25 -185 12
at winding (f _{slw})	$= 1 101 13 \text{ N/mm}^2$
Precompression at	28×1257×110113
winding $(f_{clw}) =$	2 798 288 24
	$= 1 387 6 \text{ N/mm}^2$
At site test	
Stress in longitudinal wire	= 1 286 25 - 205 69
after losses (f _{sl})	= 1 080 56 N/mm ²
T 1 D (4)	$28 \times 1257 \times 108056$
Final Precompression $(f_{cl}) =$	2 798 288 24
	$= 1.361.7 \text{ N/mm}^2$

G-6.5 Longitudinal Stress Due to Circumferential Winding

Maximum local longitudinal tensile stress during winding (see Note 1 under 7.4.1)

$= 0.284 \times 11.44 / 6 = 3.251$	1 N/mm ⁴
------------------------------------	---------------------

G-6.6 Stress Due to Beam Action

Self weight of pipe $W_s = 8,736,23$ N/m Weight of water $W_w = 11,309,76$ N/m Earth load to be considered (see Note 2 under 7.4.1)

$$= 22 \times OPD = 22 \times \frac{1384}{1000}$$

= 3 044 8 KN/m = 3 044 80 N/m Total load, W = 8 736 23 + 11 309 76 + 3 044 80 = 23 090 79 N/m

Bending moment (BM)

$$=\frac{WL^2}{8}=23\,090\,79\times5\times5\times\frac{1\,000}{8}=72\,158\,719\,\mathrm{Nm}$$

Modulus of circular $(Z_1) = 113 \ 168 \ 797 \ \text{mm}^3$ section of pipe

Stress due to beam action = $\frac{BM}{Z_1}$ = 0 637 6 N/mm²

G-6.7 Stress Due to Self Weight of Core

Self weight of core $(W_c) = 6\ 702\ 92\ \text{N/m}$ Bending moment due to mass of core (BM)

$$6\ 702\ 92 \times 5 \times 5 \times \frac{1\ 000}{8} = 20\ 946\ 625\ \text{Nmm}$$

Modulus of circular (Z.) = 84\ 297\ 111\ \text{mm}^3

section of core Stress due to self weight = $\frac{BM}{Z_2}$ =+0.248 5 N/mm²

G-6.8 Summary of Stresses in Longitudinal Direction

Stresses Due To	<i>Tensile</i> N/mm ²	Compressive N/mm ²
Maximum local longitudinal tensile stress due to bendir during winding	 n g	3 251 1
Beam action	+ 0 637 6	-0 637 6
Self weight of core	+ 0 248 5	-0 248 5
Initial precompression	+ 1 620 9	
Precompression at winding	+ 1 387 6	
Final precompression	+ 1 361 7	

Loai Combi	dıng nation	Longitudinal Stresses, N/mm ²					
		-	Ter	nsile	Compressive		
		Actual		Permissible	Actual		Permissible
a) Longitud prestress (after los	dınal s ın barrel, sses)				+1.361 7	>	Minimum residual com- pressive stress +1.0
 b) Longitud prestress winding 	dınal s durıng	-(3 251 1 + 0 248 5) + 1 387 6 = -2 112 0 -2.112 0	<	$0 56 \times (f_{p2})^{05}$ $0 56 \times 25^{05}$ = -2 800 0 -2.800 0	(0 248 5 + 1 387 6) = +1 636 1 +1.636 1	<	$0 5 \times f_{p2} 0 5 \times 25 = 12 500 0 12.500 0$
c) Longitud prestress losses pl action	dınal s after lus beam	(-0 637 6 + 1 361 7) = 0 724 1		$0 \ 34 \times (f_{ck})^{0.5} 0 \ 34 \times (40)^{0.5} = -2 \ 150 \ 3$	(0 637 6 + 1 3617) = +1 361 7		$0.5 \times f_{ck}$ 0.5×40 = 20.0
		0.724 1	<	-2.150 3	+1.361 7	<	20.0
d) Handlin winding	g before	$(-0\ 248\ 5) +$ $(+1\ 387\ 6)$ $= +1\ 139\ 1$	_	- 0 67	(0 248 5 + 1 387 6) - +1 636 1	_	$0.5 \times f_{p1}$ 0.5×15 = 7.50
		+1.139 1	<	-0.67	+1.636 1	<	7.50

G-6.9 Load Combination of Longitudinal Stresses Under Different Condition (see 7.4.1)

Actual against permissible

As the diameter of pipe is above 600 mm checking for load combination of transport and unloading is not necessary

ANNEX H

(Clause 77)

TYPICAL DESIGN OF PRESTRESSED CONCRETE PIPE OF DIAMETER 1200 mm — WINDING BY PROCESS OF DIE

H-1 Explanation of various symbols used in subsequent clauses is given in Annex J

H-2 DATA

Remaining data is same as considered in Annex G, except area of circumferential wire (A_s) being different

circumferential wire	- 1 /15 Willin
Initial stress in wire during winding (f_{si}) (see 8.3.2)	
$0.65 \times 1715 f_{s1}$	= 1 114 75 N/mm ²
Initial stress in wire during winding (f_{si}) in Annex G	
$0.75 \times 1.715 f_{s1}$	= 1 286 25 N/mm ²

Area of circumferential wire (A_s) in Annex G $A_r = 0.623 \text{ mm}^2/\text{mm}$

Area of circumferential wire (A_s) to be considered if the process for winding is die

$$A_{\rm s} = 0.623 \times \frac{1286.25}{1114.75} = 0.718.8 \,{\rm mm}^2/{\rm mm}$$

H-3 CALCULATION OF PRESTRESS IN CORE IN CIRCUMFERENTIAL DIRECTION

H-3.1 Spacing of Circumferential Wire

As the process for winding is die, 4 00 mm diameter of spiral wire is reduced to 3 45 mm to get the required tension

Allowable clear spacing (see 8.4.5)

Maximum clear spacing of wire = 50 mm Minimum clear spacing of wire = 6 mm

Area of spiral considered in $= 0.718.8 \text{ mm}^2/\text{mm}$ design (A_s)

Number of turns per meter length

$$= 0.718.8 \times \frac{1000}{0.7854} \times (3.45)^2 = 6.89$$

Centre to centre spacing of spiral wire

wire $=\frac{1\ 000}{76\ 89}$ = 13 00mm

Clear spacing of spiral wire
$$= 13 - 345$$

= 955 mm

9 55 mm is in between 50 mm and 6 mm

Hence, the area of spiral (A_{1}) considered is correct

H-3.2 Initial Compressive Stress Induced in Core (f_{cl})

$$f_{c1} = 1\ 114\ 75 \times \frac{0\ 718\ 8}{70} = 11\ 446\ 8\ \text{N/mm}^2$$

H-3.3 For futher design, the procedure as given in Annex G shall be adopted

ANNEX J

(Clause 78)

DESIGN OF PRESTRESSED CONCRETE PIPES FOR DRAINAGE, SEWERAGE AND CULVERT

J-1 Explanation of various symbols used in subsequent clauses is given in Annex K

J-2 DATA

Diameter of pipe, D	= 1 000 mm
Core thickness of pipe, t _c	= 60 mm
Coat thickness of pipe, t_b	= 22 mm
Three edge bearing load, P	= 72 6 kN/m
	= 72 600 N/m

Flexural strength of spun concrete = 6.87 N/mm^2

J-3 ASSUMPTIONS

Process of winding	Counter weight/Break
Diameter of circumferentia	l = 4 mm
wire, d_s	
Ultimate tensile strength of	= 1 715 N/mm ²
circumferential wire	
Area of circumferential wir	re, $A_{1} = 0.240 \text{ mm}^{2}/\text{mm}$

J-4 DESIGN

J-4.1 Calculation of Final Prestress Required

Calculation of moment at bottom = M $M = 0.159 \times P \times D_m$ Where, D_m = Mean diameter of pipe = $D + t_c + t_b$ = 1 000 + 60 + 22 = 1 082 mm $M = 0.159 \times 72.600 \times 1.082$ = 12 489 959 Nmm Calculation of section modulus of pipe, Z

$$Z = \frac{1}{6} \times b \times d^2$$

$$d = t_{\rm c} + t_{\rm b} = 60 + 22 = 82 \text{ mm}$$
$$Z = \frac{1}{6} \times 1\,000 \times 82 = 112\,066\,7\,\text{mm}^3$$

Stress
$$= \frac{M}{Z} = \frac{12\,489\,959}{112\,066\,7}$$

$$= 11 14 \text{ N/mm}^2$$

Final prestress = (Stress due to three edge required bearing load) – (Flexural strength of concrete) $f_{er} = 11 14 - 6 87 = 4 27 \text{ N/mm}^2$

J-4.2 Design of Circumferential Prestressing

J-4.2.1 Spacing of Circumferential Wire (see 8.4.5)

Allowable clear spacing

Maximum clear spacing of wire = 50 mm Minimum clear spacing of wire = 6 mm Area of spiral considered in design (A_s) = 0 240 mm²/mm

Number of turns per meter length

$$= 0.240 \times \frac{1.000}{19.09} \times (4)^2 = 19.09$$

Centre to centre spacing of spiral wire = $\frac{1000}{1909}$

= 52 38 mm Clear spacing of spiral wire = 52 38 - 4 = 48 38 mm

48 38 mm is in between 50 mm and 6 mm Hence, the Area of spiral (A.) considered is correct J-4.2.2 Calculation of Prestress in Core in Circumferential Direction

Initial Stress in wire during winding (f_{si}) (see 8.3.2)

 $f_{s1} = 0.75 \times 1.715 = 1.286.25 \text{ N/mm}^2$ Initial Compressive stress induced in core (f_{c1})

$$f_{\rm c1} = 1\ 286\ 25 \times \frac{0\ 240}{60} = 5\ 145\ 0\ \rm N/mm^2$$

- J-4.2.2.1 Loss of stress in wire (see Annex F)
 - a) Elastic deformation $32 \times f_{c_1} = 32 \times 51450 = 1646 \text{ N/mm}^2$
 - b) Relaxation of wire $0.08 \times f_{s1} = 0.08 \times 1.286.25 = 102.90 \text{ N/mm}^2$ c) Deformation due to creep
 - 2 5 × 5 145 0 12 86 N/mm²
 - d) Deformation due to creep and shrinkage $0\ 000\ 1 \times E_s = 0\ 000\ 1 \times 20 \times 10^4$ $=\ 20\ 00\ N/mm^2$

Total losses

1646 + 10290 + 1286 + 2000 = 15222 N/mm²

Losses at factory test

0 9 × Total loss 0 9 × 152 22

 $= 137 00 \text{ N/mm}^2$

Stress in wire at factory test (f_{ef})

 $f_{sf} = 1\ 286\ 25 - 137\ 00 = 1\ 149\ 25\ N/mm^2$ Stress in wire at Site test (f.)

 $f_{\rm s} = 1\ 286\ 25\ -\ 152\ 22\ =\ 1\ 134\ 03\ \rm N/mm^2$

Compressive stress in core at site test

$$f_{\rm cl} = 1\ 134\ 03 \times \frac{0\ 240}{60} = +4\ 536\ 1\ \rm N/mm^2$$

As final prestress (4 536 1) is more than final prestress required (4 270 0), the design is safe

J-5 For design of longitudinal prestressing, the pro cedure as given in D-1 is to be adopted

ANNEX K

(Clauses D-1, F-1, G-1 H-1 and J-1)

SYMBOLS USED IN THE DESIGN

A		Crossectional area of pipe, mm ²	$f_{\rm ck}$		Characteristic compressive strength of concrete, N/mm ²
A A _{dl}	=	Crossectional area of core, mm ² Crossectional area of longitudinal wire, mm ²	$f_{\rm pl}$	=	Compressive strength of concrete at detensioning of longitudinals. N/mm ²
А. В.	-	Area of circumferential wire, mm ² /mm Trench width, m	f_{p2}	=	Compressive strength of concrete at wind- ing, N/mm ²
C, D	=	Coefficient from Fig 4 of IS 783 Internal diameter of pipe, mm	$f_{\rm s}$	=	Final stress in circumferential wire after losses, N/mm ²
d _ı d	=	Diameter of longitudinal wire, mm Diameter of circumferential wire, mm	$f_{ m sf}$	=	Stress in circumferential wire at factory test, N/mm^2
Е́ Е	=	Modulus of elasticity of concrete, N/mm ² Modulus of elasticity of wire, N/mm ²	$f_{\rm si}$	=	Initial stress in circumferential wire during winding, N/mm ²
f _{ef}	=	Compressive stress in core concrete at fac- tory test, N/mm ²	$f_{\rm sul}$	=	Initial stress in longitudinal wire at longitu- dinal prestressing, N/mm ²
f _u	=	Initial compressive stress induced in core, N/mm ²	$f_{\rm sl}$	-	Final stress in longitudinal wire after losses, N/mm ²
f _{cil}	H	Initial precompression in core, N/mm ²	$f_{\rm slw}$	=	Stress in longitudinal wire at winding, N/mm ²
f_{clw}	=	Final precompression in core, N/mm ² Precompression at winding, N/mm ²	$f_{\rm ws}$	-	Stress in core pipe at site test due to internal pressure, N/mm ²
J _{ct}	=	Compressive stress in core concrete at site test, N/mm ²	f_{ww}	-	Stress in core pipe in operating condition due to internal pressure, N/mm ²

IS 784 : 2001

- H = Height of earth fill, m
- $K_{\rm b}$ = Density of coat concrete, N/mm³
- K_c = Density of core concrete, N/mm³
- $K_{\rm c}$ = Density of filling material, N/mm³
- $K_{\rm m}$ = Density of water, N/mm³
- L = Effective length of pipe, m
- n =• Modular ratio
- N = Number of longitudinals
- ODC = Out side diameter of core, mm
- ODP = Out side diameter of pipe, mm
- P = Axle load = 61 300 N (AA Class)
- $P_{\rm v}$ Site test pressure, N/mm²
- $P_{\rm M}$ Maximum static pressure, N/mm²
- $P_{\rm c}$ = Factory test pressure, N/mm²

- $P_{\rm w}$ = Working pressure, N/mm²
 - Mean radius of pipe wall, mm
- $T_{\rm b}$ = Coat thickness, mm
- T_c = Core thickness, mm
- $W_{\rm h}$ = Self weight of coat, N/m
- W_c = Self weight of core, N/m
- $W_{\rm e}$ = Weight of earth fill, N/mm²
- $W_1 = Live load, N/m$
- $W_{\rm c}$ = Self weight of pipe (Core + Coat), N/m
- $W_{w} = Weight of water, N/m$
- Z = Modulus of section for circumferential stress, mm³/m
- Z_1 = Modulus of circular section of pipe, mm³/m
- Z_2 = Modulus of circular section of core, mm³/m

ANNEX L

r

(Foreword)

COMMITTEE COMPOSITION

Cement Matrix Products Sectional Committee, CED 53

(hairman Representing SHRIS A REDDI Gammon India Ltd Mumbai Members SHRIP S KALANI All India Small Scale AC Pressure Pipe Manufacturer Association Secunderabad SHRI M KISHAN RI DDY (Alternate) SURI G R BHARTIKAR B G Shirke Construction Technology Ltd, Pune COLD V PADSALGIKAR (Alternate) DR B K RAO Central Building Research Institute, Roorkee DRS K AGARWAL (Alternate) SHRIP SUBRAMANIAN Central Public Works Department, New Delhi SHRIK P ABRAHAM (Alternate) SHRIS M MUNJAL Directorate General of Supplies & Disposals, New Delhi SHRIR K AGARWAL (Alternate) SHRI MAHINDRA PRASAD Engineer-in-Chief's Branch Army Headquarters, New Delhi SHRIA K AGGARWAL (Alternate) SHRIK SRIVASTAVA Eternit Everest Ltd, New Delhi SHRIS P RASTOGI Fedaration of UP Pipe Manufacturers, Lucknow SHRIAK CHADHA Hindustan Prefab Ltd, New Delhi SHRIJ R SII (Alternate) SHRI V SURESH Housing and Urban Development Corporation, New Delhi SHRIS K TANEJA (Alternate) SHRIK H GANGWAL Hyderabad Industries Ltd, Hyderabad SHRI V PATTABHI (Alternate) Municipal Corporation of Delhi, Delhi SHRIO PAGARWAL SHRIJ L DHINGRA (Alternate) Municipal Corporation of Greater Mumbai, Mumbai CHIEF ENGINEER (CEMENT CONCRETE ROAD) Dy CHIEF ENGINEER (PURCHASE) (Alternate) National Council for Cement and Building Materials Ballabgarh DR C RAJKUMAR SHRI H K JULKA (Alternate) National Test House Calcutta SHRI D K KANUNGO SHRIT CHOUDHURY (Alternate) Research, Designs & Standards Organization (Ministry of Railways) Lucknow JOINT DIRECTOR STANDARDS (B&S) ASTT DESIGN ENGINER (Alternate) SHRIM A AZEEZ Rural Electrification Corporation Ltd, New Delhi SHRI P D GAIKWAD (Alternate)

(Continued on page 27)

(Continued from page 26)

Members

Convener Shri N G Joshi

Members Suptd Engineer (Planning and Admn)

SHRIL N KAPOOR

SHRI SURINDER MOHAN

SHRIS N BASU

SHRIU C JAIN

SHRIPS GUPTA

SHRID N GARG

CHIEF ENGINEER

DRC RAJKUMAR

SHRIK C RATHOR

SHRIA V TALATI

SHRIC Y GAVHANE

SHRIK NAGARAJAN

SHRIP D KELKAR

SHRIY N CHATURVEDI SHRIV K GUPTA (Alternate)

SHRIS BASU

SHRIBK AGARWAL

SHRI SUDDHODAN ROY

SHRIS S RAMRAKHYANI SHRIS PRAKASH (Alternate)

EXECUTIVE ENGINEER (PLANNING) (Alternate) MANAGING DIRECTOR (SPUN PIPE INDIA LTD)

SHRI H S MANIK (Alternate)

SHRI R B MOHAR (Alternate)

SHRIT N UBOVEJA (Alternate)

SHRIK G DUA (Alternate)

SHRIP K SHARMA (Alternate)

SHRIS P RASTOGI (Alternate)

SHRI VIDUR BHASKAR (Alternate)

SHRI A K CHADHA (Alternate)

SHRI H K JULKA (Alternate)

JOINT DIRECTOR (B&S) CB I ADE (B&S) CS II (*Alternate*) Shri J Shanmugsundaram

ENGINEER (COMMON SERVICES) (Alternate)

SHRIS GOMATHINAYAGAM (Alternate)

SHRIA A TALATI (Alternate)

SHRI D N JOSHI (Alternate)

SHRIPRC NAIR (Alternate)

SHRIS D KANGAE (Alternate)

SHRI B SANKARASUBRAMANIA AYYAR

SHRIN P RAJAMANE DR M NEELAMEGAM (Alternate) SHRIC H SUBRAMANAN SHRI A DUTTA (Alternate) SHRIC Y GAVHANE SHRI D N JOSHI (Alternate) SHRIS HARRAMASAMY SHRI B V B PAI SHRI M S DANDWATE (Alternate) SHRIP D KELIKAR SHRIP R C NAIR SHRIS S SETHI, Director (Civ Engg)

Representing

Structural Engineering Research Centre, Chennai

Small Scale Industries Services Insitute, Ministry of Industry, New Delhi

Spun Pipes Manufacturer's Association of Maharashtra, Pune

Tamil Nadu Water Supply and Drainage Board, Chennai The Associated Cement Companies Ltd, Thane

The Indian Hume Pipe Co Ltd, Mumbai

Director General, BIS (Ex-officio Member)

Member-Secretary Shri Sanjay Pant Deputy Director (Civ Engg), BIS

Concrete Pipes Subcommittee, CED 53 2

In Personal Capacity (A/5 Adinath Antop Hill, Mumbai 400 037)

Central Public Works Department, New Delhi

Concrete Pipe Manufacturers Association, New Delhi

Delhi Water Supply and Sewage Disposal Undertaking, New Delhi

Directorate General of Supplies and Disposal, New Delhi

Engineer-in-Chief's Branch, Army Headquarters New Delhi

Engineers India Ltd New Delhi

Federation of UP Pipe Manufacturers, Lucknow

Haryana Cement Concrete Pipes & Poles Manufacturers Association New Delhi

Hindustan Prefab Ltd, New Delhi

Modi Steels Ltd, Modi Nagar Municipal Corporation of Delhi, Delhi

Municipal Corporation of Greater Mumbai, Mumbai

National Council for Cement and Building Materials, New Delhi

Public Health Engineering Department, Bhopal Research, Designs & Standards Organization (Ministry of Railways), Lucknow

Structural Engineering Research Centre, Chennai

Spun Pipe & Construction Co (Baroda) Pvt Ltd, Vadodara

Spun Pipe Manufacturers Association of Maharashtra, Pune

Tamil Nadu Water Supply and Drainage Board, Chennai The Indian Hume Pipe Co Ltd, Mumbai

Tata Consulting Engineers, Mumbai

The Kerala Premo Pipe Factory Ltd, Quilon UP Jal Nigam, Lucknow

Bureau of Indian Standards

BIS is a statutory institution established under the *Bureau of Indian Standards Act*, 1986 to promote harmonious development of the activities of standardization, marking and quality certification of goods and attending to connected matters in the country

Copyright

BIS has the copyright of all its publications. No part of these publications may be reproduced in any form without the prior permission in writing of BIS. This does not preclude the free use, in the course of implementing the standard, of necessary details, such as symbols and sizes, type or grade designations. Enquiries relating to copyright be addressed to the Director (Publications), BIS.

Review of Indian Standards

Amendments are issued to standards as the need arises on the basis of comments Standards are also reviewed periodically, a standard along with amendments is reaffirmed when such review indicates that no changes are needed, if the review indicates that changes are needed, it is taken up for revision. Users of Indian Standards should ascertain that they are in possession of the latest amendments or edition by referring to the latest issue of BIS Catalogue' and 'Standards Monthly Additions'

This Indian Standard has been developed from Doc No CED 53 (4455)

Amendments Issued Since Publication

Amer	nd No Date of Issue	Text Affected
	BUREAU OF INDIAN STANDARDS	•
Headquarte	rs	
Manak Bha Telephones	van, 9 Bahadur Shah Zafar Marg, New Delhi 110 002 2323 0131, 2323 33 75, 2323 9402	Telegrams Manaksanstha (Common to all offices)
Regional O	ffices	Telephone
Central	Manak Bhavan, 9 Bahadur Shah Zafar Marg NEW DELHI 110 002	{2323 7617 2323 3841
Eastern	1/14 C I T Scheme VII M, V I P Road, Kankurgachi KOLKATA 700 054	{2337 8499, 2337 8561 2337 8626, 2337 9120
Northern	SCO 335-336, Sector 34-A, CHANDIGARH 160 022	60 3843 60 9285
Southern	CIT Campus, IV Cross Road, CHENNAI 600 113	{2254 1216, 2254 1442 2254 2519, 2254 2315
Western	Manakalaya, E9 MIDC, Marol, Andherı (East) MUMBAI 400 093	{2832 9295, 2832 7858 2832 7891, 2832 7892
Branches	AHMEDABAD BANGALORE BHOPAL BHUBANESHW, GHAZIABAD GUWAHATI HYDERABAD JAIPUR K NALAGARH PATNA PUNE RAIKOT THIRUVANANT	AR COIMBATORE FARIDABAD ANPUR LUCKNOW NAGPUR